

**FORM
5A**Rev
09/20**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

402367194

Date Received:

10/29/2021

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 100712. Name of Operator: HIGHPOINT OPERATING CORPORATION3. Address: 555 17TH ST STE 3700City: DENVER State: CO Zip: 802024. Contact Name: Kate MillerPhone: (720) 440-6116

Fax: _____

Email: regulatory@bonanzacrk.com5. API Number 05-123-46727-007. Well Name: RSU Anschutz Fed6. County: WELDWell Number: 4-61-04-0909CS8. Location: QtrQtr: Lot 4 Section: 4 Township: 4N Range: 61W Meridian: 69. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: HYDRAULIC FRACTURING

Treatment Date: 01/26/2020 End Date: 02/03/2020 Date this Formation was Completed: 03/14/2020

Perforations Top: 14513 Bottom: 16713 No. Holes: 672 Hole size: 0.42 Open Hole: ☐

Describe the Formation Treatment, including the following: type of fluid used (gel, slickwater, etc.), type and concentration of acid used (HCl, HF, etc.), types and amounts of proppant(s) used, depth details of multiple zones, and method used to determine flowback volume.

27 stage Wet Shoe Plug and Perf: 82,995 bbl freshwater, 326 bbl 15% HCl Acid, 1,816,030 lbs 30/50 white sand, 144,430 lbs 100 mesh
A 28th stage was perforated but was not completed (14,513' - 14,573')

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 83321 Max pressure during treatment (psi): 9519

Total gas used in treatment (mcf): 0 Fluid density at initial fracture (lbs/gal): 8.34

Type of gas used in treatment: Min frac gradient (psi/ft): 0.85

Total acid used in treatment (bbl): 326 Number of staged intervals: 28

Recycled or Reused Fluids used in treatment (bbl): 0 Flowback volume recovered (bbl):

Fresh water used in treatment (bbl): 82995 Disposition method for flowback: DISPOSAL

Total proppant used (lbs): 1960460

Fracture stimulations must be reported on [FracFocus.org](https://www.fracfocus.org)

Test Information:

03/24/2020 Hours: 24 Bbl oil: 100 Mcf Gas: 50 Bbl H2O: 365

Calculated 24 hour rate: Bbl oil: 100 Mcf Gas: 50 Bbl H2O: 365 GOR: 500

Test Method: Flowing Casing PSI: 14 Tubing PSI: 307 Choke Size: 18/64

Gas Disposition: SOLD Gas Type: DRY Btu Gas: 1396 API Gravity Oil: 36

Tubing Size: 2 + 3/8 Tubing Setting Depth: 6105 Tbg setting date: 03/15/2020 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

1. The bottom of the completed interval is at 1364' FNL and 236' FEL of Section 3.
2. The wellbore beyond the unit boundary setback is physically isolated by: wet shoe sub and float collar
3. HighPoint Operating Corporation certifies that none of the wellbore beyond the unit boundary setback was completed.

Flowback data is unavailable.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Print Name: Ashley Noonan

Title: Sr. Regulatory Analyst Date: 10/29/2021 Email: regulatory@bonanzacrk.com

Attachment List

Att Doc Num Name

402367194 FORM 5A SUBMITTED

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)