


OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADO

## SUNDRY NOTICES AND REPORTS ON WELLS CONSERVATION COMMISSION

## INSTRUCTIONS

Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recompleate or abandon a well or to change plans. Within thirty (30) days after recompleation, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete ☐Report of Remedial Work ☐Notice of Intention to Change Plans ☐Report of Recompleation ☐☒ Notice of Intention to Abandon Well ☒Other ☐

(Check appropriate space)

LEASE NAME BRITTON WELL NO. D-1FIELD Mt. Hope, North WILDCAT COUNTY LoganLOCATION SW NE Section 18 Township 9 N Range 53 W Meridian 6PM

(Quarter Quarter)

2025 feet from North Section Line and 1985 feet from East Section Line

N or S

E or W

## (DETAILS OF WORK)

This well completed as a "D" sand producer in October 1958 pumping 95 BO and 16 BWPD. The decline of production was 17% per month until March of 1960 at which time formation was treated with B-10 Tretolite but did not increase production. Production at present is less than 4 BO and 23 BWPD which is below economic limit and since therevare no other prospective pay zones, it is proposed to plug and abandon by setting a rock and cement bridge above perforations, shoot off 5½ casing and pull, fill hole with heavy mud with cement plugs in bottom and top of surface casing, erect a dry hole marker, clean up, level and abandon location.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
JJD	
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

Company British-American Oil Co Date June 16, 1960

Date

Address Box 180: Denver 1, Colo Phone No AC 2 9401

Director

By James W. Hoyer Title Dist Supt

(Signature)