


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

NOTICE OF INTENTION TO DRILL




INSTRUCTIONS:

A notice of intention to drill a well shall be filed in duplicate on all Federal and Patented lands, and in triplicate on all State lands. Do not begin operations until approved copy has been received. It is mandatory that the proposed location comply with all rules and regulations of the Commission. Locate well on section grid in proper location, and indicate extent of lease. Unless operations are commenced within 180 days after the date of approval hereof, this approval to drill will become null and void.

Name of Operator The British-American Oil Producing Company Phone No. Ac. 2-9401
Address P. O. Box 180 City Denver State Colorado

How is liability secured: Well Bond (Attached) ☐; Blanket Bond ☐; Waiver ☒
(Check one)

Lease Name Britton
Well No. "D" #1
Field Name S. E. Cedar Creek Wildcat ☐
County Logan



Location C SW NE Section 18 Township 9 N Range 53 W Meridian 6 PM
(quarter quarter)
1980 feet from N Section line and 1980 feet from E Section Line
Nor S E or W

The well is located on: Patented land ☒ State land ☐ Federal land ☐

The well is located within a spaced area: Yes ☒ No ☐ Cause 41 (b'4'4')

Distance from proposed location to nearest property or lease line _____ feet.

Distance from proposed location to nearest drilling unit line _____ feet.

Objectives: "J" Sand Depth 5057'; Skull Creek Depth 5167'
Formation Estimate Formation Estimate

Proposed length of surface casing 44 feet.

Agent	<u>618</u>
Bond	<u>waived</u>
Spot	<u>Order 41</u>
600 ft.	<u>Order 41</u>
1200 ft.	<u>Order 41</u>
Wells	
Oil	
Gas	
Status	

REMARKS: PROGRAM to drill and test subject well to the "J" Sand of the Graneros Series:
Surface Casing: 9-5/8" Armco to be set at 44' GL and cemented with 1 1/2 yards ready-mixed concrete.
WOC 24 hrs. Production Casing: 5-1/2" OD 14# J-55 casing to be set through the oil producing zone of the "J" Sand. Use centralizers and rotating type scratchers through the "D" Sand and through the "J" Sand, and cement with 150 sacks 50-50 Pozmix "A" with 2% Gel. WOC 72 hrs. No coring planned.
Testing: If content of sands based on electric log is questionable, DST will be taken. Logging: Combination ES-Induction log from TD to surface casing. Detail from TD to approx. 100' above the Niobrara. Microlog from TD to 1000' above TD. Run Gamma Ray in conjunction with perforating.
Drilling Time: Use Geolograph from 210' to TD. Drift Surveys: At 50' intervals to 300'; thereafter, at 250' intervals. Standard Depth Measurements: SLM of drill pipe at approx. 150' above the Greenhorn, prior to coring, DST, and at TD. Completion Program: Whenever practicable, completion will be with rotary.

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

Date SEP 24 1958

A. J. Garrison
Director

Company BRITISH-AMERICAN Date 9-23-58

Address P. O. Box 180, Denver Phone No. Ac. 2-9401

By Thomas W. Hoyer Title District Superintendent
Signature