




# OIL AND GAS CONSERVATION COMMISSION OF THE STATE OF COLORADO



## PLUGGING RECORD

### INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator The British-American Oil Producing Co. Field Mt. Hope, East Wildcat  
Lease Name BRITTON Well No. D-1 County Logan  
Location SW, NE, Section 18 Township 9 N Range 53 W Meridian 6PM  
(Quarter Quarter)  
2025 feet from North Section line and 1985 feet from East Section Line  
N or S E or W

TOTAL DEPTH 5200'KB

DATE OF PLUGGING July 3, 1960

### DETAILS OF WORK

Filled hole with sand with 10 sax cement cap on top to 4895'KB. Shot 5½ casing off at 4270'KB and pulled, leaving 929' in hole from 5199 to 4270. Filled hole with heavy mud with a rock and cement bridge at 226-210 and a 5 sax cement plug from 18 to within cellar. The 9-5/8 surface casing was left in hole from 213 to one foot below ground level. The location cleaned up, graded and abandoned.

*Plugging checked on 11/30/60  
by Jim*

*psa oil*

AJJ	
DVR	
WRS	
HHM	
JAM	<input checked="" type="checkbox"/>
FJP	
JJD	<input checked="" type="checkbox"/>
FILE	

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date JUL 12 1960

Director

Company British-American Oil Date 7-8-60

Address Box 180, Denver 1, Colo Phone No. AC 2 9401

By Wm. W. Hope Title Dist Supt  
(Signature)