

FORM
6Rev
11/20

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

402902036

Date Received:

WELL ABANDONMENT REPORT

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set.

A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: 47120

Contact Name: Candice Barber

Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

Phone: (307) 233-4513

Address: P O BOX 173779

Fax:

City: DENVER State: CO Zip: 80217-

Email: candice_barber@oxy.com

For "Intent" 24 hour notice required,

Name:

Tel:

COGCC contact:

Email:

Type of Well Abandonment Report:



Notice of Intent to Abandon



Subsequent Report of Abandonment

API Number 05-014-14505-00

Well Name: PRIEST USX UU

Well Number: 35-1

Location: QtrQtr: NENE Section: 35 Township: 1N Range: 68W Meridian: 6

County: BROOMFIELD

Federal, Indian or State Lease Number:

Field Name: WATTENBERG

Field Number: 90750

Only Complete the Following Background Information for Intent to Abandon

Latitude: 40.012102

Longitude: -104.965546

GPS Data: GPS Quality Value: 1.3 Type of GPS Quality Value: PDOP Date of Measurement: 11/30/2021

Reason for Abandonment:



Dry



Production Sub-economic



Mechanical Problems

☐ Other

Casing to be pulled:



Yes



No

Estimated Depth:

Fish in Hole:



Yes



No

If yes, explain details below

Wellbore has Uncemented Casing leaks:



Yes



No

If yes, explain details below

Details:

Current and Previously Abandoned Zones

Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth
CODELL	7954	7966	11/08/2021	B PLUG CEMENT TOP	7870
J SAND	8390	8430	11/08/2021	B PLUG CEMENT TOP	8300

Total: 2 zone(s)

Casing History

Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top	Status
SURF	12+1/4	8+5/8	J-55	24	0	925	600	925	0	VISU
1ST	7+7/8	5+1/2	N-80	17	0	8639	250	8639	7050	CBL

Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth 8300 with 4 sacks cmt on top. CIBP #2: Depth 7870 with 4 sacks cmt on top.
CIBP #3: Depth 7439 with 4 sacks cmt on top. CIBP #4: Depth _____ with _____ sacks cmt on top.
CIBP #5: Depth _____ with _____ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set 80 sks cmt from 260 ft. to 0 ft. Plug Type: CASING Plug Tagged: ☐
Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged: ☐
Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged: ☐
Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged: ☐
Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged: ☐

Perforate and squeeze at 5320 ft. with 230 sacks. Leave at least 100 ft. in casing 4580 CICR Depth
Perforate and squeeze at 3800 ft. with 250 sacks. Leave at least 100 ft. in casing _____ CICR Depth
Perforate and squeeze at 2500 ft. with 290 sacks. Leave at least 100 ft. in casing _____ CICR Depth

(Cast Iron Cement Retainer Depth)

Set 200 sacks half in. half out surface casing from 1105 ft. to 550 ft. Plug Tagged: ☒

Set _____ sacks at surface

Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker: ☐ Yes ☒ No

Set _____ sacks in rat hole Set _____ sacks in mouse hole

Additional Plugging Information for Subsequent Report Only

Casing Recovered: 1105 ft. of 5+1/2 inch casing

Surface Plug Setting Date: 11/17/2021 Cut and Cap Date: 11/30/2021 Number of Days from Setting Surface Plug to Capping or Sealing the Well: 13

*Wireline Contractor: CUTTERS

*Cementing Contractor: SCHLUMBERGER

Type of Cement and Additives Used: _____

Flowline/Pipeline has been abandoned per Rule 1105 ☐ Yes ☐ No

Technical Detail/Comments:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: CANDICE BARBER

Title: REGULATORY ANALYST

Date: _____

Email: DJPOSTDRILL@ANADARKO.COM

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____

Date: _____

CONDITIONS OF APPROVAL, IF ANY:

COA Type

Description

--	--

Attachment List

<u>Att Doc Num</u>	<u>Name</u>
402902069	OPERATIONS SUMMARY
402902073	WELLBORE DIAGRAM
402902080	CEMENT BOND LOG
402902081	CEMENT BOND LOG
402902082	OTHER
402902084	CEMENT JOB SUMMARY
402902085	GYRO SURVEY
402902086	WIRELINE JOB SUMMARY
402902090	OTHER

Total Attach: 9 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)