




COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



(Indicate nature of data by checking below)

Notice of intention to drill _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well _____
 Report of work done on well since previous report X _____

Following is a (~~notice of intention to do work~~) December 7 19 53
 (report of work done) (On land) (patented) described as follows:

Colorado Logan Mt. Hope
 State County Field

'B' 17 C. F. Green NE 19 9N 53W -
 (Well No.) (Lease) (Sec. and $\frac{1}{4}$ Sec.) (Twp.) (Range) (Meridian)

The well is located 1000 ft. (N) of North Line and 1003 ft. (E) of _____
 (S) (W)
West Line of NE/4, Section 19-9N-53W.

The elevation above sea level is 4224 ft.

Details of Plan of Work: (State names of and expected depths to objective sands:
 Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-
 ing points, and all other important proposed work.)

12-1-53 Loaded hole with 40 barrels oil. Set bridge plug at 4950 feet. Capped with
 cement to 4947 feet. Perforated 4913 feet to 4914 feet with four 15/32" bullets.
 Perforated 4910 feet to 4913 feet with 18 15/32" bullets.

12-3-53 Flowed 78 barrels of oil no water through 16/64" choke in 24 hours from Muddy
 Sandstone. Prior production, 20 barrels oil, no water from Dakota Sandstone.

Approved: DEC 8 1953

A. J. Jensen
 Director

Company Shell Oil Company

Address Denham Building, Denver, Colorado

By _____

Title Division Production Manager

Submit reports of proposed work, for approval, on this form in Duplicate for patented
 lands and in Triplicate for school and state lands.