


COLORADO OIL AND GAS CONSERVATION COMMISSION  
SUNDRY NOTICES AND REPORTS OF WELLS



00270068



(Indicate nature of data by checking below)

333-6

Notice of intention to drill   X    
 Notice of intention to change plans \_\_\_\_\_  
 Notice of date for test of water shut-off \_\_\_\_\_  
 Report on result of test of water shut-off \_\_\_\_\_  
 Notice of intention to re-drill or repair well \_\_\_\_\_  
 Notice of intention to clean out well \_\_\_\_\_  
 Statement of shooting \_\_\_\_\_  
 Statement of perforating \_\_\_\_\_  
 Notice to pull or otherwise alter casing \_\_\_\_\_  
 Notice of intention to abandon well \_\_\_\_\_  
 Report of work done on well since previous report \_\_\_\_\_

Following is a (notice of intention to do work) October 20, 19 52  
 (~~report of work done~~) (~~On Land~~) (patented) described as follows:

Colorado Logan Mt. Hope  
 State County Field

B-17 C. F. Green NE 19 9 N 53W  
 (Well No.) (Lease) (Sec. and  $\frac{1}{4}$  Sec.) (Twp.) (Range) (Meridian)

The well is located 1000 ft. (~~N~~) of N line and 1003 ft. (E) of W  
 (S) (W)  
W line of NE/4 Section 19-9N-53W.

The elevation above sea level is   \*   ft. to be reported later.

Details of Plan of Work: (State names of and expected depths to objective sands:  
 Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-  
 ing points, and all other important proposed work.)

We propose to drill the captioned well to an approximate depth of 5100 feet, to  
 further evaluate the 'Muddy' and Dakota sandstone reservoirs underlying the C. F.  
 Green "B" lease.

8 5/8" casing will be set and cemented at approximately 600 feet.

4 1/2" casing will be cemented at approximately 5100 feet if commercial production  
 is encountered and perforate opposite the 'Muddy' or Dakota sandstone (whichever is prod-  
 uctive). We will hydrafrac and/or acid treat the productive interval if necessary.

Estimated formation tops: 'Muddy' 4866'  
 Dakota 4972'

Approved: OCT 21 1952  
[Signature]  
 Director

Company Shell Oil Company 78100  
 Address Denham Bldg., Denver, Colorado  
 By [Signature]  
 Title Division Production Manager

Submit reports of proposed work, for approval, on this form in Duplicate for patented  
 lands and in Triplicate for school and state lands.