

COLORADO OIL AND GAS CONSERVATION COMMISSION  
SUNDRY NOTICES AND REPORTS OF WELLS



(Indicate nature of data by checking below)

- Notice of intention to drill \_\_\_\_\_
- Notice of intention to change plans \_\_\_\_\_
- Notice of date for test of water shut-off \_\_\_\_\_
- Report on result of test of water shut-off \_\_\_\_\_
- Notice of intention to re-drill or repair well \_\_\_\_\_
- Notice of intention to clean out well \_\_\_\_\_
- Statement of shooting \_\_\_\_\_
- Statement of perforating \_\_\_\_\_
- Notice to pull or otherwise alter casing \_\_\_\_\_
- Notice of intention to abandon well  \_\_\_\_\_
- Report of work done on well since previous report \_\_\_\_\_

Following is a (notice of intention to do work) July 10 19 52  
(~~report of work done~~) (~~On-land~~) (patented) described as follows:

| Colorado State                                          | Logan County                           | Mt. Hope Field                          |
|---------------------------------------------------------|----------------------------------------|-----------------------------------------|
| <u>6-27</u><br>15 C. F. Green "B"<br>(Well No.) (Lease) | SE/4 Section 19<br>(Sec. and 1/4 Sec.) | 9N 53W ---<br>(Twp.) (Range) (Meridian) |

The well is located 330 ft. () of North line and 330 ft. () of West line  
(S) (W)

The elevation above sea level is 4197 DF ft.

Details of Plan of Work: (State names of and expected depths to objective sands; Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

We propose to plug and abandon the captioned well by placing cement from total depth (5065 feet) to 4768 feet opposite the Muddy and Dakota sandstone and to a point 95 feet above the top of the 'Muddy' sandstone. Then heavy mud taken from the bottom of the mud pit will be placed from 4768 feet to 480 where a cement plug will be spotted to 393 feet (opposite the bottom of the surface casing). Then heavy mud will be placed from 393 feet to within 15 feet of the surface, where a cement plug will be placed to the surface in such a manner as not to interfere with surface cultivation. Verbal approval to plug and abandon this well was granted to Mr. A. H. Wieder, Shell Division Exploitation Engineer, by Mr. J. J. Zorichak, Director of the Colorado Oil and Gas Conservation Commission by phone on July 9, 1952.

Approved: JUL 11 1952  
J. J. Zorichak  
Director

Company Shell Oil Company  
Address Denham Building, Denver, Colo.  
By [Signature]  
Title Division Production Manager

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.