




COLORADO OIL AND GAS CONSERVATION COMMISSION  
SUNDRY NOTICES AND REPORTS OF WELLS



OIL & GAS  
CONSERVATION COMMISSION

(Indicate nature of data by checking below)

256-11

Notice of intention to drill X  
 Notice of intention to change plans \_\_\_\_\_  
 Notice of date for test of water shut-off \_\_\_\_\_  
 Report on result of test of water shut-off \_\_\_\_\_  
 Notice of intention to re-drill or repair well \_\_\_\_\_  
 Notice of intention to clean out well \_\_\_\_\_  
 Statement of shooting \_\_\_\_\_  
 Statement of perforating \_\_\_\_\_  
 Notice to pull or otherwise alter casing \_\_\_\_\_  
 Notice of intention to abandon well \_\_\_\_\_  
 Report of work done on well since previous report \_\_\_\_\_

Following is a (notice of intention to do work) June 25 19 52  
 (~~report of work done~~) (~~On land~~) (patented) described as follows:

Colorado Logan Mt. Hope  
 State County Field  
15 C. F. Green "B" SE/4 Section 19 9N 53W \_\_\_\_\_  
 (Well No.) (Lease) (Sec. and  $\frac{1}{4}$  Sec.) (Twp.) (Range) (Meridian)

The well is located 330 ft. (N) of N. Line and 330 ft. (E) of \_\_\_\_\_  
 (S) (W)  
West Line.

The elevation above sea level is \* ft. \*Will be reported later.

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

We propose to drill the captioned well to a total depth of approximately 5100 feet to further evaluate the 'Muddy' and Dakota sandstone in the Mt. Hope Field.

8 5/8" casing will be set at approximately 600 feet and cemented to the surface.

4 1/2" casing will be cemented at approximately 5100 feet if commercial production is encountered and perforated opposite the 'Muddy' or Dakota sandstone; (whichever is productive). We will hydrafrac or acid treat the productive interval if necessary.

Estimated Formation Tops: Muddy 4870 feet  
 Dakota 4975 feet

Approved: JUN 27 1952  
[Signature]  
 Director

Company Shell Oil Company  
 Address Denham Building Denver 2, Colo.  
 By [Signature]  
 Title Division Production Manager

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.