



COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS

RECEIVED
APR 26 1955
OIL & GAS
CONSERVATION COMMISSION

(Indicate nature of data by checking below)

- Notice of intention to drill (attach plat) _____
- Notice of intention to change plans _____
- Notice of date for test of water shut-off _____
- Report on result of test of water shut-off _____
- Notice of intention to re-drill or repair well _____
- Notice of intention to clean out well _____
- Statement of shooting _____
- Statement of perforating and Plugging back. _____
- Notice to pull or otherwise alter casing _____
- Notice of intention to abandon well _____
- Report of work done on well since previous report _____

Locate Well Correctly

		x	
		20	

Notice to do work Land: Fee and Patented
 Report of work done State Lease No. 41660

Colorado State Logan County Walker Field

3 (Well No.) C. F. Green (Lease) NE/4 (1/4 Sec.) 20 (Sec.) 9N (Twp.) 53W (Range) 6th PM (Meridian)

The Well is located 990 Ft. (N) of Section Line and 1650 Ft. (E) of Section Line. SE/4 NW/4 NE/4 (S) (W)

The elevation above sea level is 4186 Ft.

Details of Plan of Work: (State names of and expected depths to objective sands. Show sizes, weights, and length of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

April 15, 1955 - Pulled 2" tubing. Ran Baker model "k" magnesium bridging plug on wire line set at ~~4267~~ 4967'.

SIXTH PERFORATIONS

Perforated 5 1/2" OD casing 4948'-60' with 48 shots by McCullough jet shots. Spotted a cement plug above bridging plug 4967'-62'.

Plug Bake Total Depth 4962'.

Ran 2" tubing and Lane-Wells packer. Packer not set bottom of tubing 4874'.

April 19, 1955 - Flowed thru 2" tubing 13 hours, on 3/4" choke 27 bbls. oil, 10 bbls. water, 1/2 MMCF gas per day. FTP 550#; CP 560#.

April 20, 1955 - Flowed thru 2" tubing 24 hours, on 3/4" choke 18 bbls. water, no oil, 2-1/2 MMCF gas per day. FTP 576#; CP 570#.

Commenced on April 15, 1955
Date Completed on April 20, 1955.

Approved: APR 26 1955
[Signature]
Director

Company Skelly Oil Company
Address Box 310 - Sterling, Colorado
By [Signature]
Title District Superintendent.

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.

