



00270126

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADORECEIVED
MAR 4 1965OIL & GAS
CONSERVATION COMMISSION

PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Skelly Oil Company Field Walker Wildcat _____
Lease Name C. F. Green Well No. 3 County Logan
Location SE/4 NW/4 NE/4 Section 20 Township 9N Range 53W Meridian 6
(Quarter Quarter)
990 feet from N Section line and 1650 feet from E Section Line
N or S E or W

TOTAL DEPTH 4960'DATE OF PLUGGING February 5, 1965

DETAILS OF WORK

Sand	4960' to 4893'
5 sacks of cement	4893' to 4853'
Mud laden fluid	4853' to 412'
15 sacks of cement	412' to 372'
Mud laden fluid	372' to 12'
5 sacks of cement	12' to Base of cellar
Surface soil	Cellar to Surface

Left in hole:

403' of 10-3/4", 29#, Armco SW casing
1398' of 5-1/2", 15½#, 8R, J-55, R-2, SS casing

DVR	
WRS	
HHM	
JAM	
FJP	✓
JJD	✓
FILE	

EX
Oil
Prod.

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date MAR 8 1965

Director

Company SKELLY OIL COMPANY Date March 3, 1965

P. O. Box 649

Address McCook, Nebraska Phone No 345-3510By C. F. Bass Title Dist. Supt.
(Signature) C. F. Bass