

FORM
6Rev
11/20

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

402914612

Date Received:

WELL ABANDONMENT REPORT

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set.

A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: 100322

Contact Name: Kevin Monaghan

Name of Operator: NOBLE ENERGY INC

Phone: (970) 3812990

Address: 1001 NOBLE ENERGY WAY

Fax:

City: HOUSTON State: TX Zip: 77070

Email: kevin.monaghan@nblenergy.com

For "Intent" 24 hour notice required,

Name:

Tel:

COGCC contact:

Email:

Type of Well Abandonment Report:



Notice of Intent to Abandon



Subsequent Report of Abandonment

API Number 05-123-24833-00

Well Name: MCCLELLAN

Well Number: 3-35

Location: QtrQtr: SWSW

Section: 3

Township: 4N

Range: 65W

Meridian: 6

County: WELD

Federal, Indian or State Lease Number:

Field Name: WATTENBERG

Field Number: 90750

Only Complete the Following Background Information for Intent to Abandon

Latitude: 40.337870

Longitude: -104.654510

GPS Data: GPS Quality Value: 5.1 Type of GPS Quality Value: Date of Measurement: 04/22/2007

Reason for Abandonment:



Dry



Production Sub-economic



Mechanical Problems

☐ Other

Casing to be pulled:



Yes



No

Estimated Depth:

Fish in Hole:



Yes



No

If yes, explain details below

Wellbore has Uncemented Casing leaks:



Yes



No

If yes, explain details below

Details:

Current and Previously Abandoned Zones

Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth
CODELL	7036	7052	08/24/2021	B PLUG CEMENT TOP	6975

Total: 1 zone(s)

Casing History

Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top	Status
SURF	12+1/4	8+5/8	NA	24	0	447	215	447	0	VISU
1ST	7+7/8	4+1/2	M80	11.6	0	7235	647	7235	2868	CBL

Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth 6975 with 2 sacks cmt on top. CIBP #2: Depth 6707 with 2 sacks cmt on top.
CIBP #3: Depth 4027 with 2 sacks cmt on top. CIBP #4: Depth _____ with _____ sacks cmt on top.
CIBP #5: Depth _____ with _____ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set 35 sks cmt from 2400 ft. to 1954 ft. Plug Type: CASING Plug Tagged: ☐
Set 100 sks cmt from 952 ft. to 738 ft. Plug Type: OPEN HOLE Plug Tagged: ☒
Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged: ☐
Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged: ☐
Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged: ☐

Perforate and squeeze at 2500 ft. with 155 sacks. Leave at least 100 ft. in casing 2400 CICR Depth

Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth

Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth

(Cast Iron Cement Retainer Depth)

Set 272 sacks half in. half out surface casing from 738 ft. to 0 ft. Plug Tagged: ☒

Set _____ sacks at surface

Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker: ☐ Yes ☐ No

Set _____ sacks in rat hole Set _____ sacks in mouse hole

Additional Plugging Information for Subsequent Report Only

Casing Recovered: 1730 ft. of 4+1/2 inch casing

Surface Plug Setting Date: 09/01/2021 Cut and Cap Date: 12/01/2021 Number of Days from Setting Surface Plug to Capping or Sealing the Well: 91

*Wireline Contractor: Ranger

*Cementing Contractor: Ranger

Type of Cement and Additives Used: Class G Neat

Flowline/Pipeline has been abandoned per Rule 1105 ☐ Yes ☒ No

Technical Detail/Comments:

COAs for production have been addressed.
Procedure email attached.

Perfs @ 2500' and 2000' for CICR @ 2400'
CSG Cut/Pull @ 1730'

Form 17 DocNum: 402782449
Form 27 DocNum: 402776470
Form 42 DocNum: 402781124
Form 44 DocNum: Flowline will be abandoned.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Lauren Hoff
Title: HSE Reg Affairs Coord Date: _____ Email: DenverRegulatory@nblenergy.com

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Date: _____

CONDITIONS OF APPROVAL, IF ANY:

<u>COA Type</u>	<u>Description</u>

Attachment List

<u>Att Doc Num</u>	<u>Name</u>
402914617	CEMENT JOB SUMMARY
402914618	OPERATIONS SUMMARY
402914619	OTHER
402914620	CEMENT BOND LOG
402914621	WELLBORE DIAGRAM
402914622	WIRELINE JOB SUMMARY

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)