




00241909

COLORADO
WELD COUNTY
WILDCAT



Twp 3N-56W
Section 29
C NW SE

OPR: Utah Southern

WELL #: 1 Grabill

ELEV: 4506 KB

*TOPS: Log ~~5544~~

Niobrara 4924
Timpas 5206
Carlile 5276
Greenhorn 5431
Graneros 5544
Brown Lime 5642
D Sand 5742
J Sand 5821

DSTS. & CORES:

Grd 5743-63, rec 1' sd,
17' sh. Grd 5822-45,
rec 8' hard, tight sd,
slight gas odor, 9' sd,
fair to good permeability,
oil stain & gas odor, 12'
sh, bentonitic, 5' clay
filled sd. DST 5824-28
1 hr, gas in 4 min, est
1333 MCFGPD, rec 50'
gassy mud cut oil, 630'
gassy, slightly dist
cut fresh wtr, FP 160-
420#, SIP (20 min) 1420#
HP 3300#.

SPUD: 4-29-55

COMPL: 6-17-55

TD: 5895

PB:

CSG: 10-3/4" @ 192 w/125
5 1/2" @ 5894 w/250

PERF:

5823-29.

PROD. ZONE:

INIT. PROD: Est flow 2000 MCFGPD w/
considerable dist, comp as
shut in gas well.

"J SAND GAS DISCOVERY - NEW FIELD"

(Contr: Trans-Era)

*For Electric Logs on Rocky Mountain Wells—Ask Us! Log Order # A963.

7-14-55