




COLORADO OIL AND GAS CONSERVATION COMMISSION  
SUNDRY NOTICES AND REPORTS OF WELLS



OIL & GAS  
CONSERVATION COMMISSION

(Indicate nature of data by checking below)

Notice of intention to drill \_\_\_\_\_  
Notice of intention to change plans \_\_\_\_\_  
Notice of date for test of water shut-off \_\_\_\_\_  
Report on result of test of water shut-off \_\_\_\_\_  
Notice of intention to re-drill or repair well \_\_\_\_\_  
Notice of intention to clean out well \_\_\_\_\_  
Statement of shooting \_\_\_\_\_  
Statement of perforating \_\_\_\_\_  
Notice to pull or otherwise alter casing \_\_\_\_\_  
Notice of intention to abandon well \_\_\_\_\_  
Report of work done on well since previous report X

November 10 19 53

Following is a (~~notice of intention to do work~~) (On land)  
(report of work done) (~~patented~~) described as follows:

Colorado	Logan	Mt. Hope
State	County	Field
1	Kirk 'B'	SE/4 18 9N 53W -
(Well No.)	(Lease)	(Sec. and $\frac{1}{4}$ Sec.) (Twp.) (Range) (Meridian)

The well is located 678 ft. (N) of South Line and 659 ft. (E) of  
(S) (W)  
West Line of SE/4, Section 18-9N-53W.

The elevation above sea level is 4254 ft.

Details of Plan of Work: (State names of and expected depths to objective sands:  
Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-  
ing points, and all other important proposed work.)

10-26-53 Spudded.  
10-30-53 Ran and cemented 8 5/8" casing at 597 feet with 200 sacks.  
11-8-53 Ran Schlumberger electric survey and microlog. Mud from 5208 (TD) to 612  
(15 feet below surface casing). Cement plug to 582 feet. Mud from 582 feet  
to 10 feet where plug was set to surface in such a manner as not to interfere  
with surface cultivation. P&A COMPLETE.

Schlumberger Formation Tops

Niobrara	4118
Muddy	4997
Dakota	5105

Approved: \_\_\_\_\_

NOV 13 1953

Director

Company Shell Oil Company

Address Denham Building, Denver, Colorado

By W. W. Wiedler

Title For Division Production Manager

Submit reports of proposed work, for approval, on this form in Duplicate for patented  
lands and in Triplicate for school and state lands.