

Contractor Stuarco Drilling Co. Top Choke 1 1/2"
 Rig No. 6 Bottom Choke 9/16"
 Spot SW-NW Size Hole 7 7/8"
 Sec. 29 Size Rat Hole _____
 Twp. 12N Size & Wt. D. P. 1 1/2"
 Rng. 52W Size Wt. Pipe 3 5/8"
 Field N. W. Peetz I. D. of D. C. 2 1/2"
 County Logan Length of D. C. 116'
 State Colorado Total Depth 5305'
 Elevation 4533 KB Interval Tested 5130-5140
 Formation "D" Sand Type of Test Straddle

Tool Open @ 7:15 P M.
 Tool Open 3 min. before Initial Shut In 20 min.
 Tool Open 120 min. Total Final Shut In 30 min.
 B. H. T. 11480 Gravity _____
 Mud Wt. 10 Viscosity 95

TOOL SEQUENCE

RECEIVED


AUG 13 1968

COLO. OIL & GAS CONS. COMM.

5124-----○
 5130-----○
 5140-----○
 5305-----○



00300274



PRD Make	<u>Kuster AK-1</u>		
No. <u>988</u>	Cap. <u>4700</u>	@ <u>5120</u>	
Press	Field	Corrected	
IH A	2726	2735	
FH G	2559	2650	
PF B	105	101	
IF D		127	
FF E	293	301	
ISIP C	657	676	
FSIP F	645	649	
Pressure Below Bottom Packer Bled To	1775	1775	

Our Tester: Carl J. MoehrWitnessed By: Roland Young

RECOVERY IN PIPE

DID WELL FLOW - Gas Yes Oil No Water No

980' fluid in pipe.

50' oil & water cut mud = 0.3 bbls.

930' Gas cut water with very slight trace of oil = 9.50 bbls.

.....


REMARKS: Strong steady blow, gas to surface in 4 minutes. Maximum blow 4# on
 1 1/2" orifice = 480,000 Cu. Ft. per day, decreasing slightly to 2# on 1 1/2" orifice
 = 332,000 Cu. Ft. per day.

Initial Shut-in - 5 mins. 667 lbs.; 10 mins. 671 lbs.; 15 mins. 674 lbs.; 20 mins.
 676 lbs.

Final Shut-in - FF 301 lbs.; 5 mins. 587 lbs.; 10 mins. 612 lbs.; 15 mins. 630 lbs.;
 20 mins. 638 lbs.; 25 mins. 644 lbs.; 30 lbs. 649 lbs.

Operator Rex MonahanADDRESS 111 S. 3d St., Sterling, Colo.Well Name and No. Winnie Smith # 2Ticket No. 9278Date 7-11-68DST No. 1
No. Final Copies 5

BOTTOM CHART
T-9278 R-VT-23



Rex Monahan
Minnie Smith #2 DST # 1

This recorder blanked off below the bottom packer and since pressure bled to only 1775 lbs., which is more than the shut-in pressure, the bottom packer held. Recorder No. VT-33