

Donnelly Casing Pulling Co.

PHONE LA 2-1410

P. O. BOX 648

BOB DONNELLY

STERLING, COLORADO



00255345

SOLD TO ART SKAER

INVOICE DATE 1/31/61

WELL ~~XXXXXXXXXXXX~~ Kelly

INVOICE NO. 12

3780' ----- 5 1/2" O. D. Casing ----- @ .25 per joint ----- \$945.00
20 sacks cement ----- 1.60 per sack ----- 32.00

Net due \$977.00

- THANK YOU -

WELL REPORT

Date	Remarks
1/26/61	Raised mast, dug cellar, run 150 gal sand, dumped 2 gal rock, run 5 sacks cement, rigged up, got 40" tension.
1/27/61	Worked pipe from 40" tension, shot casing @ 3975', 3870', 3755' got loose, pulled 1 joint.
1/28/61	Pulled 25 joints.
1/30/61	Pulled 75 joints.
1/31/61	Pulled 23 joints, dumped 5 sacks cement on bottom, run rock mud, dumped 5 sacks, run rock, mudded up to 20', dumped 5 sacks cement on top, tallied pipe. PLUGGING COMPLETE.

RECEIVED
MAR 21 1961
OIL & GAS
CONSERVATION COMMISSION