


OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF COLORADO

## PLUGGING RECORD

OIL & GAS  
CONSERVATION COMMISSION

## INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Don M. Rounds Company Field Pebble Wildcat  
Lease Name Elenz Well No. 3 County Logan  
Location C NW SE Section 21 Township 12N Range 52W Meridian 6th P.M.  
(Quarter Quarter)  
1980 feet from S Section line and 1980 feet from E Section Line  
N or S E or W

TOTAL DEPTH 5238'DATE OF PLUGGING January 11, 1959

## DETAILS OF WORK

Ran drill pipe to bottom. Displaced 25 sax cement to bottom and plugged hole from 5170' to 5238'. Filled hole with heavy mud to base of surface casing. Plugged bottom of surface pipe from 360' to 380' with 15 sax cement. Filled remainder of surface pipe with heavy mud. Dumped 5 sax cement in top of surface casing, and welded steel cap on top of surface pipe below plow depth.

AJJ	
DVR	
WRS	
HHM	
JAM	✓
FJP	
JJD	✓
FILE	

05-075-07309



Called re: prior approval to plug 2-2-59

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

FEB - 2 1959

Date

Director

Company Don M. Rounds CompanyDate Jan. 29, 1959Address 925 Petroleum Club Bldg.Denver 2, ColoradoPhone No. MA 3-0296By [Signature]  
(Signature)Title Prod. Engineer