

OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

RECEIVED

NOV 10 1970

COLO. OIL & GAS CONS. COMM.

PLUGGING RECORD



00290688

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Marathon Oil Company Field Pebble Wildcat
Lease Name D. Meier Well No. 1 County Logan
Location Lot #1 Section 21 Township 12N Range 52W Meridian
(Quarter Quarter)
3320 feet from south Section line and 787 feet from east Section Line
N or S E or W

TOTAL DEPTH 5239DATE OF PLUGGING 10-16-70

DETAILS OF WORK

D. Meier #1 was plugged and abandoned by Donnelly Casing Pullers as follows:
Placed a 14-gallon sand plug from 5214' to 5200'. Placed an 8-sack cement plug from 5200' to 5117'. Shot 5½" casing at 4000', 3750', 3500', 3200', and 3039' where the casing became free. Recovered 3029' of 5½" casing leaving 2192' of 5½" casing in the hole from 3039' to 5230'. Filled the hole with 214 barrels of mud-laden fluid from 5117' to 303'. Placed a 15-sack cement plug from 303' to 272' in the bottom of the surface pipe. Filled the surface casing with 59 barrels of mud-laden fluid from 272' to 21'. Placed a 10-sack cement plug from 21' to surface.

DVR	
FJP	✓
HHM	✓
JAM	✓
JJD	✓

Ex Oil Prod.

I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved:

Date

NOV 12 1970

Director

Company Marathon Oil Company Date 10-28-70

P. O. Box 39

Address Sidney, Nebraska 69162 Phone No. 254-5561

Area

By Robert Van Cleave Title Superintendent

(Signature)

R. L. Van Cleave