



OFFICE OF STATE OIL INSPECTOR
SUNDRY NOTICES AND REPORTS OF WELLS
LOCATED ON PRIVATE LANDS

2 approved copies
returned 7-10-51
LB

124A

(Indicate nature of data by checking below)

Notice of intention to drill.....
Notice of intention to change plans.....
Notice of date for test of water shut-off.....
Report on result of test of water shut-off.....
Notice of intention to re-drill or repair well.....
Notice of intention to clean out well.....
Statement of shooting.....
Statement of perforating.....
Notice to pull or otherwise alter casing.....
Notice of intention to abandon well..... X
Report of work done on well since previous report.....

July 7 19 51

Following is a (notice of intention to do work) (On land)
(~~report of work done~~) (patented) described as follows:

State	County	Field
Colorado	Logan	Wildcat
I	W. A. Johnson	NW of Sec. 20
(Well No.)	(Lease)	(Sec. and $\frac{1}{4}$ Sec.)
		12 N
		(Twp.)
		52 W
		(Range)
		6th
		(Meridian)

The well is located 330 ft. (N) of S Line and 330 ft. (X) of E Line
(X) (W)

The elevation above sea level is 4502 ft. Ground

Details of Plan of Work: (State names of and expected depths to objective sands:
Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-
ing points, and all other important proposed work.)

Well commenced June 19, 1951. 187 feet of 10 3/4- inch surface casing was set and
cemented June 20, 1951. 9-inch hole drilled with rotary to total depth of 5610 at
the base of the Lakota Sand. All formations dry. Hole will be filled with extra heavy
mud from total depth of 5610 to the base of the surface pipe at 187 feet. Hole will
be bridged with a wooden plug and 15 sacks of cement placed in well from 187 feet to
157 feet. Surface casing will be filled with heavy mud from 157 feet to 20 feet,
and hole will be filled with 10 sacks of cement from 20 feet to surface. A ten foot
joint of heavy 3-inch pipe will be imbedded six feet in the cement with 4 feet show-
ing above ground level to permanently mark location. Screw cap will enclose top of
pipe.

Well was drilled by the E. K. Carey Drilling Company of Denver, Colorado. Work was
done under the supervision of Joe Hurley, Drilling Superintendent for the E. K. Carey
Drilling Company.

Approved: July 9, 1951

State Oil Inspector

Company The Derby Oil Company
(Of Wichita, Kansas)

Address 705 Denver National Bank Building
Denver, Colorado

By Dean C. Wellman

Title Mgr. Denver Office

Submit reports of proposed work, for approval, on this form in Duplicate.