

1136 - Spuds Blvd.

240



OFFICE OF STATE OIL INSPECTOR
SUNDRY NOTICES AND REPORTS OF WELLS
LOCATED ON PRIVATE LANDS

(Indicate nature of data by checking below)

- Notice of intention to drill.....
- Notice of intention to change plans.....
- Notice of date for test of water shut-off.....
- Report on result of test of water shut-off.....
- Notice of intention to re-drill or repair well.....
- Notice of intention to clean out well.....
- Statement of shooting.....
- Statement of perforating.....
- Notice to pull or otherwise alter casing.....
- Notice of intention to abandon well.....
- Report of work done on well since previous report..... **X**

Following is a (notice of intention to drill / report of work done) March 5 19 52
(patented) described as follows:

<u>Colorado</u>	<u>Logan</u>	<u>Wildcat</u>
State	County	Field
<u>1</u>	<u>M. W. Dimery</u>	<u>21 SW/4</u>
(Well No.)	(Lease)	(Sec. and 1/4 Sec.)
		<u>12 North</u>
		(Twp.)
		<u>53 West</u>
		(Range)
		<u>6th P.M.</u>
		(Meridian)

The well is located 2310 ft. (N) of South line and 330 ft. (E) of West line
of Section 21

The elevation above sea level is 4645 ft.

Details of Plan of Work: (State names of and expected depths to objective sands; Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

Spudded 2-9-52. Set 300' of 10-3/4" casing @ 312.
Niobrara Shale @ 4569'; "D" Sand 5399' - 5499'; and "J"
Sand 5517' - 5605'. Total Depth 5607'.
Plugged as follows: 5580--15 sks cement; mud; 5450--15 sks
cement; mud; 5400-300 mud; 300-270 15 sks cement; plugged
top with 10 sks cement.
Plugged and abandoned on February 29, 1952.

Approved: MAR 10 1952
[Signature]
State Oil Inspector
DIRECTOR

Company Carl L. Brazell
Address 709 Colorado Building
Denver, Colorado
By.....
Title.....

Submit reports of proposed work, for approval, on this form in Duplicate.