



RECEIVED
AUG 6 1953
OIL & GAS
CONSERVATION COMMISSION

OGCC - FORM 1

COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS

(Indicate nature of data by checking below)

- Notice of intention to drill _____
- Notice of intention to change plans _____
- Notice of date for test of water shut-off _____
- Report on result of test of water shut-off _____
- Notice of intention to re-drill or repair well _____
- Notice of intention to clean out well _____
- Statement of shooting _____
- Statement of perforating _____
- Notice to pull or otherwise alter casing _____
- Notice of intention to abandon well _____ **XX**
- Report of work done on well since previous report _____

Following is a ~~(notice of intention to do work)~~ (report of work done) AUGUST 5, 19 53 (on land) described as follows:
(patented)

COLORADO State LOGAN County WILDCAT Field

1 (Well No.) CAREY (Lease) 26 NW/4 (Sec. and 1/4 Sec.) 9N (Twp.) 53W (Range) 6th (Meridian)

The well is located 1650 ft. **(X)** of NL and 990 ft. **(E)** of WL
(S) **(W)**

of Sec. 26 or NE SW NW

The elevation above sea level is 4161 ft.

Details of Plan of Work: (State names of and expected depths to objective sands:
Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.

TOTAL DEPTH 5155'. 10 3/4" CASING WAS SET AT 253' AND CEMENTED WITH 200 SACKS CEMENT. A 75 SACK CEMENT PLUG WAS LAID 5000 TO 4800'. A 50 SACK CEMENT PLUG WAS LAID 300 TO 190'. PLACED 25 SACK CEMENT PLUG IN TOP OF CASING. A METAL CAP WAS WELDED IN TOP OF CASING AND A 3" x 4' LENGTH OF PIPE ERECTED FOR A MARKER. WELL PLUGGED AND ABANDON 7-30-53.

Approved: AUG 6 1953

Company McDERMOTT & BARNHART

J. J. Brink
Director

Address DRAWER 352 STERLING, COLO.

By Paul Speck, Jr.
Title Dist. Clerk

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.

T