

# STATE ANTELOPE E14-31-30XRLNB

## Current WBD

660' FSL2462' FEL SWSE 31 5N 62W 6th PM

Lat 40.350873 Long -104.365929

Weld County, Colorado

API #05-123-51160

Spud date 1/31/2022

0 KB

0 GL

8.625", 24#/ft Wt, J-55, 1724', 13.5" hole  
No Casing set

350' cement plug, set from 650' MD – 300' MD  
295 sacks Class G cement, 15.8 ppg slurry, 1.184 cu ft/sk yield,  
197 BBLs of 17.5 ppg Spacer

Measured depth of proposed sidetrack kick-off point: 300' MD

Updated

2/1/2022