

# Longs Peak Resources LLC

**Well Name:** Lazy D ZN 03-09

**Field:** Codell

**Date:** 9/9/2010

**Location:** 40.949850, -104.760390

**County:** Weld

**State:** Colorado

**Surface Location:** 40.949850, -104.760390

**Lateral TD Location:**

**Completed:** 9/20/2010

**Elevation:** 5894'

**KB:** 18.0'

**API #:** 05-123-31832

CSG	Bit Size	OD	ID	Drift	Grade	Thd	Wt/ft	Cap (bbl/ft)	Burst	Collapse	Top	Set
Surface	12.5"	8.625"	8.097"	7.972"	J-55	-	24#	0.0773	2950	1370	0	2325'
Prod.	7.875"	5.5"	4.548"	4.423"	-	-	26#	0.0212	11,730	15,030	0	9600'
Liner	6.125"	4.5"	4.00"	3.875"	P110	-	11.6#	0.01554	10,690	7580	-	9615'

Well temporarily abandoned  
Bridge plug set @ 9572'

5.5" 26# @ 0' to 9600'

4 1/2" 11.6# P-110 Liner 9615'MD

TVD 10,000'MD

8 5/8" 36# J-55 LTC @ 2325' MD

12 1/2" hole

6 1/8" hole

TOC 8140'