

Cement Verification Report - Cementer's Well Service, Inc.



P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

COGCC Operator Guidance **RULE #308.A.B(2)A.ii**

CLIENT: Great Western Operating	Cementer's FIELD TICKET #	400116-D
---------------------------------	---------------------------	----------

Requested Operator Guidance:

Well Name & Number	Lease	Raindance	Well No.	FC 23 - 272HC
--------------------	-------	-----------	----------	---------------

Well API Number	05-123-51583			
-----------------	--------------	--	--	--

Job Date	7/15/21	Time on	16:00	24 hr time
----------	---------	---------	-------	------------

Job Type	New Well Surface			
----------	------------------	--	--	--

Cementing Company	Cementer's Well Service, Inc	Contact	Nate Kvamme - 303-324-4296	
-------------------	------------------------------	---------	----------------------------	--

Ambient conditions	clear / rain / snow / other	90	temp deg F	
--------------------	-----------------------------	----	------------	--

Slurry Description				
--------------------	--	--	--	--

a) Purpose	Surface - 9 5/8" 40# CSG, 13 1/2" hole			
------------	--	--	--	--

b) Cement Class	Type I / II			
-----------------	-------------	--	--	--

c) Cement Yield	1.61	cuft / sk		
-----------------	------	-----------	--	--

d) Cement Density	13.9	PPG		
-------------------	------	-----	--	--

e) Number of sks	920	sks (94# equiv)		
------------------	-----	-----------------	--	--

f) Mix Fluid Type				
-------------------	--	--	--	--

Water / Cement	8.5	Gal / sk		
----------------	-----	----------	--	--

g) Slurry mixed	263.8	BBLs slurry		
-----------------	-------	-------------	--	--

h) Additives used	1.50%	CaCl2	3.00%	Bentonite
-------------------	-------	-------	-------	-----------

Total Water Used	361.2	BBLs H2O		
------------------	-------	----------	--	--

i) Displacement Fluid Vol	155.0	BBLs H2O		
---------------------------	-------	----------	--	--

j) Method of Placement				
------------------------	--	--	--	--

k) Set Depth	2,048	feet (ft)		
--------------	-------	-----------	--	--

l) Stage tool depth	n/a			
---------------------	-----	--	--	--

m) Float Collar Depth	2,004	feet (ft)		
-----------------------	-------	-----------	--	--

n) Designed Top of Cement	n/a	to surface feet (ft)		
---------------------------	-----	----------------------	--	--

o) Centralizer depths	18 Centralizers at Following Depths: 96.66, 220.19, 342.42, 466.25, 589.69, 713.17, 836.39, 959.57, 1080.42, 1204.19, 1326.72, 1450.47, 1567.42, 1691.47, 1815.31, 1937.22, 1977.57, 2032.03			
-----------------------	--	--	--	--

Charts - (pressure, density, pump rate)

Landed Plug @	1705	psi	Final Lift Pressure @	575	psi
---------------	------	-----	-----------------------	-----	-----

Cement Density (as weighed during job) @	13.9	PPG
--	------	-----

Job notes

a) Plug down	<input checked="" type="radio"/> Y / <input type="radio"/> N	Time	18:42	24 hr time
--------------	--	------	-------	------------

b) Floats held	<input checked="" type="radio"/> Y / <input type="radio"/> N	7/15/21		
----------------	--	---------	--	--

c) Full Returns	<input checked="" type="radio"/> Y / <input type="radio"/> N	Lost Circulation	<input checked="" type="radio"/> Y / <input type="radio"/> N
-----------------	--	------------------	--

d) Cement to surface	<input checked="" type="radio"/> Y / <input type="radio"/> N	40.0	BBLs to surface
----------------------	--	------	-----------------

e) If no returns, top off	n/a	BBLs		
---------------------------	-----	------	--	--

f) Top off detail	-			
-------------------	---	--	--	--

Surface Cement Job Report - Cementer's Well Service, Inc.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

DATE: DATE: 7/15/21



Great Western Operating Company, LLC

Lease: Raindance
Well: FC 23 - 272HC
API# 05-123-51583

Date & Time On
7/15/21
16:00

Item	Event	Date	Time (24 hr)	Density (PPG)	Pump Rate (BPM)	Incremental (Line Item) Volume (BBLs)	Cumulative Volume (BBLs)	Pressure (PSI)	Comment
Pre-job	1 Call Out	7/15/21	13:00						Great Western Call out w/ 3 hr notice
	2 Leave Yard	7/15/21	15:15						Cementer's leaves yard to travel to location
On Location: Pre-job	3 Arrive On Location	7/15/21	16:00						Arrive on location
	4 Spot Trucks	7/15/21	16:05						Spot trucks on location
	5 Rig Up	7/15/21	16:07						Rig up water & Cementer's Bulk Truck, prep pump and mixing operation
	6 Safety Meeting	7/15/21	16:12						Pre-job safety meeting with IKON12 rig crew, GWO company man & Cementer's crew
	7 Rig Up	7/15/21	16:17						Rig up cement head w/plug
	8 Fill Lines	7/15/21	16:19	8.34	2.00				Fill lines with up to 5 bbls of fresh water
Initial Job Start	9 Pressure Test	7/15/21	0:00	8.34	-			-	Pressure test pumps and lines
	10 Pump Spacer	7/15/21	16:45	8.34	4.00	20	20	-	Pump dye fresh water @ 20 BBLs
Cementing	11 Pump Cement	7/15/21	16:50	13.90	4.00	263.82	283.82	45	Pump Cement @ 920 SKS
									Type I/II cement with 1.5% CaCl ₂ & 3.0% Bentonite @ 1.61 cuft/sk & 13.9 PPG
Displacement	12 Drop Plug	7/15/21	18:02			n/a			Shut down cementing operation & release top plug
	13 Initial Displacement	7/15/21	18:04	8.34	2.00	4.00	287.82	-	Send plug with 4.0 BBLs H ₂ O @ 2.0 BPM
	14 Plug Drop Verification	7/15/21	18:08			n/a			Visual verification plug released from head
	15 Displacement	7/15/21	18:10	8.34	5.00	100.99	384.80	80-450	Continued Displacement with total fresh water @ 155.0 BBLs H ₂ O
	16 Spacer To Surface	7/15/21	18:32	8.34	5.00	104.99	388.80	385	Identified Spacer, looking for Cement / green water
	17 Cement To Surface	7/15/21	18:35	8.34	5.00	114.99	398.80	390	Identify Cement to surface w/ 40 BBLs back
	18 Drop Rate	7/15/21	18:40	8.34	2.50	144.99	428.80	400	Drop rate to 2.5 BPM for last 10 BBLs of Displacement to land plug
Casing Test	19 Land Plug	7/15/21	18:42	8.34	2.50	154.99	438.80	1,705	Land Plug @ 1,705 PSI
									with final lift pressure @ 575 PSI
Casing Test	20 Casing Test	7/15/21	18:42	n/a	0	0	0	1,705	Start 30 min casing test w/ pressure @ 1,705 PSI
			18:52	n/a	0	0	0	1,720	10 min into casing test, pressure @ 1,720 PSI
			19:02	n/a	0	0	0	1,742	20 min into casing test, pressure @ 1,742 PSI
			19:12	n/a	0	0	0	1,756	30 min into casing test, pressure @ 1,756 PSI
Post Job & Testing	24 Check Floats	7/15/21	19:13	n/a	0	0	0	1	BBLs back (.25-1BBL expected)
	25 End Job	7/15/21	19:15						Bleed off pressure, job complete
	26 Safety Meeting	7/15/21	19:17						Pre-rig down safety meeting, wash up equipment
	27 Rig Down	7/15/21	19:20						Rig down Cementer's Equipment, leave location

Cementer's Well Service, Inc.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712



Great Western Operating Company, LLC

Surface Cement Job Graph

COMPANY DETAILS

Date	7/15/21	API #	05-123-51583	Well No.	FC 23 - 272HC
County	Weld	State	CO	Lease	Raindance

Client Great Western Operating Company, LLC

Contact / email

JOB DETAILS

TIME ON	16:00	24 hr	Depth	2,048	ft.	Pressure Test @	1,705	psi
START TIME	16:30	7/15/21	Bottom of Surface	2,048	ft.	10 min	1,720	psi
END TIME	19:45	7/15/21	Plug Landed @	2,005	ft.	20 min	1,742	psi
			Plug Landed @	18:42	24 hr	30 min	1,756	psi

SUMMARY GRAPH

