

OPERATOR: K.P. Kauffman Compnay Inc.
WELL: UPRR 43 Pan Am I #27
FIELD: Wattenberg
API # 05-123-09913
LEASE #: _____
UIC #: _____

CNTY: Weld FTG: _____
STATE: CO Q-Q: NWSW
SPUD: 2/20/1980 SEC.: 10
COMP: 3/21/1981 TWS: 1N
STATUS: PR RGE: 68W
WBD DATE: 2/3/2022 BY: _____

CURRENT WELLBORE DIAGRAM

KBE: 5110 '
KB: 10 '
GLE: 5100 '

TD (ft): 5350 '
PBTD (ft): 5303 '

12 1/2" Hole
8 5/8, 24# Csg @ 245 '
Cmtd w/ 200 sxs

7 7/8" Hole
4 1/2, 10.5# Csg @ 5340 '
Cmtd w/ 400 sxs

TOC @ 3320 '
Calc

Sussex-Shannon Perfs
4704'-4790'

PBTD (ft): 5303 '
TD (ft): 5350 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/2</u>	<u>8 5/8</u>	<u>24</u>		<u>0</u>	<u>245</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>		<u>0</u>	<u>5340</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	TALLY (ft)	JTS

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES
<u>SX-SN</u>	<u>4704</u>	<u>4790</u>	<u>148</u>

WELLWORK HISTORY

Shannon

78120 gal cond x 37800 gal water, 192000# 20/40 sand,
36000# 10/20 sand, flush w/ 3486 gal water

Sussex

78540 gal cond x 38220 gal water, 192000# 20/40 sand,
flush x 3528 gal water