

OPERATOR: K.P. Kauffman Compnay Inc.
WELL: UPRR 43 Pan Am I #33
FIELD: Wattenberg
API # 05-123-09978
LEASE #:
UIC #:

CNTY: Weld FTG:
STATE: CO Q-Q: NESW
SPUD: 7/18/1980 SEC.: 10
COMP: 3/22/1981 TWS: 1N
STATUS: PR RGE: 68W
WBD DATE: 2/3/2022 BY:

CURRENT WELLBORE DIAGRAM

KBE: 5126 '
KB: 4 '
GLE: 5122 '
TD (ft): 5370 '
PBTD (ft): 5308 '

12 1/2" Hole
8 5/8, 24# Csg @ 842 '
Cmtd w/ 350 sxs

7 7/8" Hole
4 1/2, 10.5# Csg @ 5370 '
Cmtd w/ 400 sxs

TOC @ 3350 '
Calc

Sussex-Shannon Perfs
4744'-5266'

PBTD (ft): 5308 '
TD (ft): 5370 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
<u>12 1/4</u>	<u>8 5/8</u>	<u>24</u>	<u>J-55</u>	<u>0</u>	<u>842</u>
<u>7 7/8</u>	<u>4 1/2</u>	<u>10.5</u>	<u>J-55</u>	<u>0</u>	<u>5370</u>

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	TALLY (ft)	JTS

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES
<u>SX-SN</u>	<u>4744</u>	<u>5266</u>	<u>240</u>

WELLWORK HISTORY

Shannon

75600 gal gel oil x 39480 water - 192000# 10/20 sand
and 36000# 20/40 sand - flush w/ 1050 gal water

Sussex

77952 gal oil x 40782 gal water - 192000# 20/40 sand
and 36000# 10/20 sand - flush 2982 gal water