

FORM
2
Rev
12/20

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402952376

(SUBMITTED)

Date Received:

02/16/2022

APPLICATION FOR PERMIT TO:

Drill Deepen Re-enter Recomplete and Operate

Amend

TYPE OF WELL OIL GAS COALBED OTHER: _____

Refile

ZONE TYPE SINGLE ZONE MULTIPLE ZONES COMMINGLE ZONES

Sidetrack

Well Name: STATE SEVENTY HOLES Well Number: 34-32-34XRL
 Name of Operator: BONANZA CREEK ENERGY OPERATING COMPANY LLC COGCC Operator Number: 8960
 Address: 410 17TH STREET SUITE #1400
 City: DENVER State: CO Zip: 80202
 Contact Name: JEFF ANNABLE Phone: (303)312-8529 Fax: ()
 Email: JANNABLE@CIVIRESOURCE.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20120018

WELL LOCATION INFORMATION

Surface Location

QtrQtr: NENW Sec: 5 Twp: 4N Rng: 62W Meridian: 6
 Footage at Surface: 584 Feet FNL/FSL 2591 Feet FEL/FWL
 Latitude: 40.347400 Longitude: -104.350520
 GPS Data: GPS Quality Value: 2.2 Type of GPS Quality Value: PDOP Date of Measurement: 09/22/2018
 Ground Elevation: 4535
 Field Name: WATTENBERG Field Number: 90750

Well Plan: is Directional Horizontal (highly deviated) Vertical

If Well plan is Directional or Horizontal attach Deviated Drilling Plan and Directional Data.

Subsurface Locations

Top of Productive Zone (TPZ)
 Sec: 32 Twp: 5N Rng: 62W Footage at TPZ: 10 FSL 1850 FEL
 Measured Depth of TPZ: 6605 True Vertical Depth of TPZ: 6155 FNL/FSL FEL/FWL

Base of Productive Zone (BPZ)
 Sec: 34 Twp: 5N Rng: 62W Footage at BPZ: 10 FSL 950 FEL
 Measured Depth of BPZ: 18154 True Vertical Depth of BPZ: 6155 FNL/FSL FEL/FWL

Bottom Hole Location (BHL)
 Sec: 34 Twp: 5N Rng: 62W Footage at BHL: 10 FSL 950 FEL
 FNL/FSL FEL/FWL

LOCAL GOVERNMENT PERMITTING INFORMATION

County: WELD Municipality: N/A

Is the Surface Location of this Well in an area designated as one of State interest and subject to the requirements of § 24-65.1-108 C.R.S.? Yes

Per § 34-60-106(1)(f)(I)(A) C.R.S., the following questions pertain to the Relevant Local Government approval of the siting of the proposed Oil and Gas Location.

SB 19-181 provides that when "applying for a permit to drill," operators must include proof that they sought a local government siting permit and the disposition of that permit application, or that the local government does not have siting regulations. § 34-60-106(1)(f)(I)(A) C.R.S.

Does the Relevant Local Government regulate the siting of Oil and Gas Locations, with respect to this Location? Yes No

If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location.

The disposition of the application filed with the Relevant Local Government is: Approved Date of Final Disposition: 10/25/2019

Comments: Approved permit is WOGLA19-0161.

SURFACE AND MINERAL OWNERSHIP AT WELL'S OIL & GAS LOCATION

Surface Owner of the land at this Well's Oil and Gas Location: Fee State Federal Indian

Mineral Owner beneath this Well's Oil and Gas Location: Fee State Federal Indian

Surface Owner Protection Financial Assurance (if applicable): _____ Surety ID Number (if applicable): _____

MINERALS DEVELOPED BY WELL

The ownership of all the minerals that will be developed by this Well is (check all that apply):

- Fee
 State
 Federal
 Indian
 N/A

LEASE INFORMATION

Using standard QtrQtr, Section, Township, Range format describe one entire mineral lease as follows:

* If this Well is within a unit, describe a lease that will be developed by the Well.

* If this Well is not subject to a unit, describe the lease that will be produced by the Well.

(Attach a Lease Map or Lease Description or Lease if necessary.)

Township 5 North Range 62 West
Section 32: All

Total Acres in Described Lease: 640 Described Mineral Lease is: Fee State Federal Indian

Federal or State Lease # OG-108197

SAFETY SETBACK INFORMATION

Distance from Well to nearest:

Building: 5280 Feet
Building Unit: 5280 Feet
Public Road: 5280 Feet
Above Ground Utility: 5280 Feet

INSTRUCTIONS:

- Specify all distances per Rule 308.b.(1).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit – as defined in 100 Series Rules.

Railroad: 5280 Feet
Property Line: 584 Feet

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	407-3290	880	T4N62W: SEC 2-NWNW, SEC 3-N2N2, SEC 4-N2N2, SEC 5-N2NE; T5N62W: SEC 32-SESW& S2SE, SEC 33-S2S2, SEC 34-S2S2

Federal or State Unit Name (if appl): _____ Unit Number: _____

SUBSURFACE MINERAL SETBACKS

Enter 5280 for distance greater than 1 mile.

Is this Well within a unit? Yes

If YES:

Enter the minimum distance from the Completed Zone of this Well to the Unit Boundary: 950 Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well within the same unit permitted or completed in the same formation: 0 Feet

If NO:

Enter the minimum distance from the Completed Zone of this Well to the Lease Line of the described lease: _____ Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well producing from the same lease and permitted or completed in the same formation: _____ Feet

Exception Location

If this Well requires the approval of a Rule 401.c Exception Location, enter the Rule or spacing order number and attach the Exception Location Request and Waivers. _____

SPACING & FORMATIONS COMMENTS

DRILLING PROGRAM

Proposed Total Measured Depth: 18154 Feet

TVD at Proposed Total Measured Depth 6155 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 263 Feet No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No If yes, attach an H₂S Drilling Plan unless a plan was already submitted with the Form 2A per Rule 304.c.(10).

Will there be hydraulic fracture treatment at a depth less than 2,000 feet in this well? No

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: Annular Preventor Double Ram Rotating Head None

Beneficial reuse or land application plan submitted? _____

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	N/A	42	0	80	100	80	0
SURF	12+1/4	9+5/8	J-55	36	0	1500	400	1500	0
1ST	8+1/2	5+1/2	P-110	20	0	18154	2427	18154	1500

Conductor Casing is NOT planned

POTENTIAL FLOW AND CONFINING FORMATIONS

Zone Type	Formation /Hazard	Top M.D.	Top T.V.D.	Bottom M.D.	Bottom T.V.D.	TDS (mg/L)	Data Source	Comment
Groundwater	Alluvium	0	0	69	69	1001-10000	USGS	USGS-402053104240501
Groundwater	Laramie-Fox Hills	69	69	185	185	501-1000	Groundwater Atlas	USGS HA-650 (Robson et al, 1981)
Confining Layer	Pierre Shale	185	185	325	325			
Groundwater	Upper Pierre Aquifer	325	325	1309	1295	501-1000	Electric Log Calculation	Seventy Holes 23-5 (05-123 -35671-0000)
Confining Layer	Pierre Shale	1309	1295	3348	3285			
Hydrocarbon	Parkman	3348	3285	3399	3335			Not productive.
Confining Layer	Pierre Shale	3399	3335	6195	6015			
Subsurface Hazard	Sharon Springs	6195	6015	6605	6155			
Hydrocarbon	Niobrara	6605	6155	18154	6155			

OPERATOR COMMENTS AND SUBMITTAL

Comments

The distance to the completed portion of the nearest well in the same unit on the "Spacing & Formations" tab is 0' since this is the only well within the drilling and spacing unit.

The distance to the nearest well belonging to another operator on the "Drilling & Waste Plans" tab was measured to RSU Anschutz Fed 4-62-2-0108C (API #05-123-46654). This distance was measured in 2-dimensional space.

Changes made to the permit: Landing Point/Bottom-Hole were moved, updated spacing information, updated casing plan. updated offset well evaluation.

The Surface Use Agreement is attached to the original scout card. Location has been constructed

This application is in a Comprehensive Area Plan _____ CAP #: _____
 Oil and Gas Development Plan Name _____ OGDID ID#: _____
 Location ID: 445479
 I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.
 Signed: _____ Print Name: JEFF ANNABLE
 Title: Lead, Regulatory Date: 2/16/2022 Email: JANNABLE@CIVIRESOURCE

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved: _____ Director of COGCC _____ Date: _____
 Expiration Date: _____

API NUMBER
05 123 50050 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

<u>COA Type</u>	<u>Description</u>

Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Drilling/Completion Operations	Alternative Logging Program: One of the first wells drilled on the pad will be logged with open-hole resistivity log with gamma-ray log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall state "Alternative Logging Program - No open-hole logs were run" and shall clearly identify the type of log and the well (by API#) in which open-hole logs were run.
2	Drilling/Completion Operations	Anti-collision: Operator will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within 150 feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators prior to drilling

Total: 2 comment(s)

Attachment List

Att Doc Num	Name
402952929	OffsetWellEvaluations Data
402952931	WELL LOCATION PLAT
402952933	DIRECTIONAL DATA
402952934	DEVIATED DRILLING PLAN

Total Attach: 4 Files

General Comments

User Group	Comment	Comment Date
		Stamp Upon Approval

Total: 0 comment(s)



Public Comments

No public comments were received on this application during the comment period.

