

FORM  
2

Rev  
12/20

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402862162

(SUBMITTED)

Date Received:

02/17/2022

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

Amend ☐

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER: \_\_\_\_\_

Refile ☒

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: Flaherty Well Number: 13-7-2  
Name of Operator: CONFLUENCE DJ LLC COGCC Operator Number: 10518  
Address: 1001 17TH STREET #1250  
City: DENVER State: CO Zip: 80202  
Contact Name: Brittany Rothe Phone: (303)226-9519 Fax: ( )  
Email: brothe@confluencelp.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20160056

WELL LOCATION INFORMATION

Surface Location

QtrQtr: SESW Sec: 18 Twp: 4N Rng: 62W Meridian: 6  
Footage at Surface: 432 Feet FSL 1678 Feet FWL  
Latitude: 40.306370 Longitude: -104.370540  
GPS Data: GPS Quality Value: 1.9 Type of GPS Quality Value: PDOP Date of Measurement: 03/03/2020  
Ground Elevation: 4563  
Field Name: WATTENBERG Field Number: 90750

Well Plan: is ☐ Directional ☒ Horizontal (highly deviated) ☐ Vertical

If Well plan is Directional or Horizontal attach Deviated Drilling Plan and Directional Data.

Subsurface Locations

Top of Productive Zone (TPZ)

Sec: 13 Twp: 4N Rng: 63W Footage at TPZ: 2354 FNL 470 FEL  
Measured Depth of TPZ: 7444 True Vertical Depth of TPZ: 6301 FNL/FSL FEL/FWL

Base of Productive Zone (BPZ)

Sec: 13 Twp: 4N Rng: 63W Footage at BPZ: 2295 FNL 470 FWL  
Measured Depth of BPZ: 11850 True Vertical Depth of BPZ: 6301 FNL/FSL FEL/FWL

Bottom Hole Location (BHL)

Sec: 13 Twp: 4N Rng: 63W Footage at BHL: 2295 FNL 470 FWL  
FNL/FSL FEL/FWL

## LOCAL GOVERNMENT PERMITTING INFORMATION

County: WELD

Municipality: N/A

Is the Surface Location of this Well in an area designated as one of State interest and subject to the requirements of § 24-65.1-108 C.R.S.? Yes

Per § 34-60-106(1)(f)(I)(A) C.R.S., the following questions pertain to the Relevant Local Government approval of the siting of the proposed Oil and Gas Location.

SB 19-181 provides that when "applying for a permit to drill," operators must include proof that they sought a local government siting permit and the disposition of that permit application, or that the local government does not have siting regulations. § 34-60-106(1)(f)(I)(A) C.R.S.

Does the Relevant Local Government regulate the siting of Oil and Gas Locations, with respect to this Location? ☒ Yes ☐ No

☒ If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location.

The disposition of the application filed with the Relevant Local Government is: Approved Date of Final Disposition: 07/20/2018

Comments: The WOGLA was approved on July 20, 2018.

## SURFACE AND MINERAL OWNERSHIP AT WELL'S OIL & GAS LOCATION

Surface Owner of the land at this Well's Oil and Gas Location: ☐ Fee ☒ State ☐ Federal ☐ Indian

Mineral Owner beneath this Well's Oil and Gas Location: ☐ Fee ☒ State ☐ Federal ☐ Indian

Surface Owner Protection Financial Assurance (if applicable): \_\_\_\_\_ Surety ID Number (if applicable): \_\_\_\_\_

### MINERALS DEVELOPED BY WELL

The ownership of all the minerals that will be developed by this Well is (check all that apply):

- ☒ Fee  
☐ State  
☐ Federal  
☐ Indian  
☐ N/A

### LEASE INFORMATION

Using standard QtrQtr, Section, Township, Range format describe one entire mineral lease as follows:

\* If this Well is within a unit, describe a lease that will be developed by the Well.

\* If this Well is not subject to a unit, describe the lease that will be produced by the Well.

(Attach a Lease Map or Lease Description or Lease if necessary.)

T4N R63W Sec. 13: All

Total Acres in Described Lease: 640 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # \_\_\_\_\_

### SAFETY SETBACK INFORMATION

Distance from Well to nearest:

Building: 2511 Feet  
Building Unit: 4071 Feet  
Public Road: 776 Feet  
Above Ground Utility: 712 Feet

#### INSTRUCTIONS:

- Specify all distances per Rule 308.b.(1).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit – as defined in 100 Series Rules.

Railroad: 5280 Feet  
Property Line: 432 Feet

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	407-2372	640	T4N R63W Sec.13: All

Federal or State Unit Name (if appl): Unit Number:

## SUBSURFACE MINERAL SETBACKS

Enter 5280 for distance greater than 1 mile.

Is this Well within a unit? Yes

If YES:

Enter the minimum distance from the Completed Zone of this Well to the Unit Boundary: 470 Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well within the same unit permitted or completed in the same formation: 167 Feet

If NO:

Enter the minimum distance from the Completed Zone of this Well to the Lease Line of the described lease: Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well producing from the same lease and permitted or completed in the same formation: Feet

## Exception Location

☐ If this Well requires the approval of a Rule 401.c Exception Location, enter the Rule or spacing order number and attach the Exception Location Request and Waivers.

## SPACING & FORMATIONS COMMENTS

## DRILLING PROGRAM

Proposed Total Measured Depth: 11850 Feet TVD at Proposed Total Measured Depth 6301 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 733 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No If yes, attach an H<sub>2</sub>S Drilling Plan unless a plan was already submitted with the Form 2A per Rule 304.c.(10).

Will there be hydraulic fracture treatment at a depth less than 2,000 feet in this well? No

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

Beneficial reuse or land application plan submitted?

Reuse Facility ID: or Document Number:

**CASING PROGRAM**

Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	A52A	43	0	80	400	80	0
SURF	13+1/2	9+5/8	J-55	36	0	1650	674	1650	0
1ST	8+1/2	5+1/2	P110	20	0	11850	1064	11850	4000

☐ Conductor Casing is NOT planned

**POTENTIAL FLOW AND CONFINING FORMATIONS**

Zone Type	Formation /Hazard	Top M.D.	Top T.V.D.	Bottom M.D.	Bottom T.V.D.	TDS (mg/L)	Data Source	Comment
Groundwater	Laramie-Fox Hills	0	0	250	250	501-1000	USGS	Top & bottom depth from DWR
Groundwater	Upper Pierre	250	250	1525	1503	1001-10000	Other	COGCC: Upper Pierre Aquifer Water Quality Study, Project 2141
Confining Layer	Pierre Shale	1525	1503	4331	3916			
Hydrocarbon	Sussex	4331	3916	4602	4147			
Confining Layer	Pierre Shale	4602	4147	5174	4634			
Hydrocarbon	Shannon	5174	4634	5307	4747			
Confining Layer	Pierre Shale	5307	4747	6883	6073			
Subsurface Hazard	Sharon Springs	6883	6073	7072	6191			
Hydrocarbon	Niobrara	7072	6191	7444	6301			

**OPERATOR COMMENTS AND SUBMITTAL**

Comments Distance from completed zone of this wellbore to nearest completed zone of an offset well within the same unit permitted or completed in the same formation was measured in 2D to the proposed Confluence DJ LLC Flaherty 13-3-4.

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells was measured to the producing Latham U41-Y44-14HNB (API No. 05-123-49907-00) operated by Bonanza Creek.

This is a Form 2 Refile.

Changes to the original approved Form 2 are: Name change, top of productive interval, bottom hole location, total depth, casing and cement program.

This location has been built; therefore, an OGDG is not required.

This application is in a Comprehensive Area Plan No CAP #: \_\_\_\_\_

Oil and Gas Development Plan Name \_\_\_\_\_ OGDG ID#: \_\_\_\_\_

Location ID: 442024

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Andrea Gross

Title: Permit Agent Date: 2/17/2022 Email: agross@upstreampm.com



Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_  
Expiration Date: \_\_\_\_\_

**API NUMBER**

05 123 47461 00

**Conditions Of Approval**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

**COA Type**

**Description**

**Best Management Practices**

**No BMP/COA Type**

**Description**

1	Drilling/Completion Operations	Anti-collision: Operator will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within 150 feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators prior to drilling.
2	Drilling/Completion Operations	Logging: The Middlepark 18-21-3L (API No. 05-123-47444-00), well drilled on the pad was logged with an open-hole Resistivity Log and Gamma Ray Log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "No open-hole logs were run. The Middlepark 18-21-3L (API No. 05-123-47444-00) is the well in which open-hole logs were run."

Total: 2 comment(s)

**Attachment List**

**Att Doc Num**

**Name**

402942787	DEVIATED DRILLING PLAN
402942789	DIRECTIONAL DATA
402956095	OffsetWellEvaluations Data
402956113	WELL LOCATION PLAT

Total Attach: 4 Files

**General Comments**

**User Group**

**Comment**

**Comment Date**

		Stamp Upon Approval
--	--	---------------------

Total: 0 comment(s)

## Public Comments

No public comments were received on this application during the comment period.

