

FORM
2

Rev
12/20

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402728757

(SUBMITTED)

Date Received:

03/29/2022

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

Amend ☐

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER: _____

Refill ☒

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: BJU G35 FED Well Number: 25C-35-496
Name of Operator: CAERUS PICEANCE LLC COGCC Operator Number: 10456
Address: 1001 17TH STREET #1600
City: DENVER State: CO Zip: 80202
Contact Name: Reed Haddock Phone: (720)880-6369 Fax: (303)565-4606
Email: rhaddock@caerusoilandgas.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20130021

WELL LOCATION INFORMATION

Surface Location

QtrQtr: SWNE Sec: 35 Twp: 4S Rng: 96W Meridian: 6
Footage at Surface: 2109 Feet FNL/FSL 2248 Feet FEL/FWL FEL
Latitude: 39.660279 Longitude: -108.134545
GPS Data: GPS Quality Value: 1.8 Type of GPS Quality Value: PDOP Date of Measurement: 06/14/2021
Ground Elevation: 8166
Field Name: GRAND VALLEY Field Number: 31290

Well Plan: is ☒ Directional ☐ Horizontal (highly deviated) ☐ Vertical

If Well plan is Directional or Horizontal attach Deviated Drilling Plan and Directional Data.

Subsurface Locations

Top of Productive Zone (TPZ)

Sec: 35 Twp: 4S Rng: 96W Footage at TPZ: 384 FSL 1492 FEL
Measured Depth of TPZ: 8454 True Vertical Depth of TPZ: 7880 FNL/FSL FEL/FWL

Base of Productive Zone (BPZ)

Sec: 35 Twp: 4S Rng: 96W Footage at BPZ: 350 FSL 1586 FEL
Measured Depth of BPZ: 11900 True Vertical Depth of BPZ: 11325 FNL/FSL FEL/FWL

Bottom Hole Location (BHL)

Sec: 35 Twp: 4S Rng: 96W Footage at BHL: 350 FSL 1586 FEL
FNL/FSL FEL/FWL

LOCAL GOVERNMENT PERMITTING INFORMATION

County: GARFIELD

Municipality: N/A

Is the Surface Location of this Well in an area designated as one of State interest and subject to the requirements of § 24-65.1-108 C.R.S.? No

Per § 34-60-106(1)(f)(I)(A) C.R.S., the following questions pertain to the Relevant Local Government approval of the siting of the proposed Oil and Gas Location.

SB 19-181 provides that when "applying for a permit to drill," operators must include proof that they sought a local government siting permit and the disposition of that permit application, or that the local government does not have siting regulations. § 34-60-106(1)(f)(I)(A) C.R.S.

Does the Relevant Local Government regulate the siting of Oil and Gas Locations, with respect to this Location? ☐ Yes ☒ No

☐ If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location.

The disposition of the application filed with the Relevant Local Government is: Waived Date of Final Disposition: _____

Comments: Caerus Piceance LLC has contacted Garfield County, the local government with jurisdiction over the siting of this proposed oil and gas location and determined that per the Garfield County Land Use and Development Code, Table 3-403, "Oil and Gas Drilling and Production" and "Hydraulic Fracturing, Remote Surface Location" are a use by right or Exempt from Land Use Regulation at this site. Garfield County's disposition is not required for the purposes of this submittal.

SURFACE AND MINERAL OWNERSHIP AT WELL'S OIL & GAS LOCATION

Surface Owner of the land at this Well's Oil and Gas Location: ☒ Fee ☐ State ☐ Federal ☐ Indian

Mineral Owner beneath this Well's Oil and Gas Location: ☐ Fee ☐ State ☒ Federal ☐ Indian

Surface Owner Protection Financial Assurance (if applicable): _____ Surety ID Number (if applicable): _____

MINERALS DEVELOPED BY WELL

The ownership of all the minerals that will be developed by this Well is (check all that apply):

- ☐ Fee
☐ State
☒ Federal
☐ Indian
☐ N/A

LEASE INFORMATION

Using standard QtrQtr, Section, Township, Range format describe one entire mineral lease as follows:

* If this Well is within a unit, describe a lease that will be developed by the Well.

* If this Well is not subject to a unit, describe the lease that will be produced by the Well.

(Attach a Lease Map or Lease Description or Lease if necessary.)

Sec. 35, T4S-R96W - S/2 and other lands.

Total Acres in Described Lease: 818 Described Mineral Lease is: ☐ Fee ☐ State ☒ Federal ☐ Indian

Federal or State Lease # COC69557

SAFETY SETBACK INFORMATION

Distance from Well to nearest:

Building: 5280 Feet

INSTRUCTIONS:

- Specify all distances per Rule 308.b.(1).
- Enter 5280 for distance greater than 1 mile.

Building Unit: 5280 Feet
Public Road: 2644 Feet
Above Ground Utility: 5280 Feet
Railroad: 5280 Feet
Property Line: 3217 Feet

- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit – as defined in 100 Series Rules.

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	1-229		

Federal or State Unit Name (if appl): Big Jimmy

Unit Number: COC74105X

SUBSURFACE MINERAL SETBACKS

Enter 5280 for distance greater than 1 mile.

Is this Well within a unit? Yes

If YES:

Enter the minimum distance from the Completed Zone of this Well to the Unit Boundary: 350 Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well within the same unit permitted or completed in the same formation: 430 Feet

If NO:

Enter the minimum distance from the Completed Zone of this Well to the Lease Line of the described lease: Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well producing from the same lease and permitted or completed in the same formation: Feet

Exception Location

☐ If this Well requires the approval of a Rule 401.c Exception Location, enter the Rule or spacing order number and attach the Exception Location Request and Waivers.

SPACING & FORMATIONS COMMENTS

DRILLING PROGRAMProposed Total Measured Depth: 12186 FeetTVD at Proposed Total Measured Depth 11611 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 1240 Feet ☐ No well belonging to another operator within 1,500 feetWill a closed-loop drilling system be used? YesIs H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater thanor equal to 100 ppm? No If yes, attach an H₂S Drilling Plan unless a plan was already submitted with the Form 2A per Rule 304.c.(10).Will there be hydraulic fracture treatment at a depth less than 2,000 feet in this well? NoWill salt sections be encountered during drilling? NoWill salt based (>15,000 ppm Cl) drilling fluids be used? NoWill oil based drilling fluids be used? NoBOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

Beneficial reuse or land application plan submitted? _____

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	30	20	A252	54#	0	100	218	100	0
SURF	14+3/4	9+5/8	J55	36#	0	3000	710	3000	0
1ST	8+3/4	4+1/2	HCP110	11.6#	0	12186	1465	12186	3000

☐ Conductor Casing is NOT planned**POTENTIAL FLOW AND CONFINING FORMATIONS**

Zone Type	Formation /Hazard	Top M.D.	Top T.V.D.	Bottom M.D.	Bottom T.V.D.	TDS (mg/L)	Data Source	Comment
Groundwater	Green River	0	0	1800	1714	501-1000	CGS	
Confining Layer	Wasatch	2671	2515	5900	5489			
Hydrocarbon	Wasatch G	5929	5515	6200	5765			The Wasatch G is a non-productive zone in the referenced area of the basin
Confining Layer	Ft. Union	6273	5832	8400	7826			
Hydrocarbon	Ohio Creek	8454	7880	8600	8026	>10000	Produced Water Sample	
Hydrocarbon	Williams Fork	8688	8114	11300	10725	>10000	Produced Water Sample	
Hydrocarbon	Cameo	11400	10825	11900	11325	>10000	Produced Water Sample	
Hydrocarbon	Rollins	11986	11411	12186	11611	>10000	Produced Water Sample	

OPERATOR COMMENTS AND SUBMITTAL

Comments

This pad has been built and has a valid Form 2A. It is anticipated that drilling 16 wells on this pad will run from mid December 2021 to mid June 2022. This re-file request is necessary because approved permits will expire before Caerus Piceance LLC can finish drilling ALL wells permitted on the NPM G35-496 pad. This wellbore is in the 16th well slot. Previously submitted (June 22, 2021) directional plans, data, cement, and casing design stay the same. No new revisions required.

This application is in a Comprehensive Area Plan _____

CAP #: _____

Oil and Gas Development Plan Name _____

OGDP ID#: _____

Location ID: 335904

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Reed Haddock

Title: Regulatory Lead

Date: 3/29/2022

Email: rhaddock@caerusoilandgas.co

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved: _____

Director of COGCC

Date: _____

Expiration Date: _____

API NUMBER

05 045 24341 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

Best Management Practices

No BMP/COA Type

Description

1	Planning	Alternative Logging Program: One of the first wells drilled on the pad will be logged with open-hole resistivity log with gamma-ray log from TD into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs will state Alternative Logging Program - No open-hole logs were run.
2	Planning	The associated well pad Location ID: 335904 was approved on May 29, 2020 by the COGCC. The BLM White River Field Office (WRFO) approved the Application for Permit to Drill (APD) for this well on July 10, 2020, under the land use planning review of the WRFO Record of Decision and Approved Resource Management Plan (ROD/RMP), as amended by the WRFO Oil and Gas Development Plan Approved Resource Management Plan Amendment and the Northwest Colorado Greater Sage-Grouse Approved RMPA. Please reference the attached WRFO Environmental Assessment from July 2020 and the Decision Record approved by the WRFO BLM on July 6, 2020, which specifically addresses the criteria in which the associated well pad was evaluated and approved.
3	Drilling/Completion Operations	Closed loop system will be used. No pits will be built. Caerus will ensure 150 percent secondary containment for any potential volume of fluids that may be released.

Total: 3 comment(s)

Attachment List

<u>Att Doc Num</u>	<u>Name</u>
402744214	OTHER
402744217	OTHER
402841195	OffsetWellEvaluations Data

Total Attach: 3 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Engineer	Need offset well evaluation.	10/05/2021

Total: 1 comment(s)



Public Comments

No public comments were received on this application during the comment period.

