

API:05-081-06987

Duncan Unit 2 #4
Sec 20, T12N-R100W
Moffat County, Colorado

updated: CSL 2/22/07
spud date: 9/16/00
completion date: 10/9/00

6829' KB

WO: 1/07 to C/O and lower tbg

Surface Casing Data

8-5/8", 24#, J-55
Set @ 866' w/ 300 sx cmt
Hole Size: 11"

Tubing Data

KB to tbg hanger 11'
1 ABB Vetco Hanger
48 jts 2-3/8" EUE Tbg
94 jts 2-3/8" EUE Tbg (estimated)
1 XN nipple @ 4451.02'
1 jt 2-3/8" EUT Tbg
1 notched collar @ 4483.14
EOT @ 4483.54'

Production Casing Data

4-1/2", 11.6#, N-80
Set @ 5050' w/ 1585 sx cmt.
Hole Size: 7-7/8"

Wasatch
2380-3495'

2380-2384'
2945-2950'
3290-3295'
3388-3393'
3490-3495'

4 spf, 120deg phased

40329 # 20/40 Jordan sand.
53059 # 20/40 Jordan sand.
45155 # 20/40 Jordan sand
treated: 296 bbls 60Q N2 foam & 39441# proppant
treated: 302 bbls 60Q N2 foam & 39835# proppant

Ft. Union
4042-4052'

4042-4052'

4 spf, 120deg phased, convential frac stimulation

treated: 630 bbl 65Q N2 foam & 109051# proppant

Lewis

4564-4645'

4564-4567, 4606-4610, 4641-4645

4 spf, 120deg phased, convential frac stimulation

treated: 1012 bbl 65Q N2 foam & 164515# proppant

PBTD = 5006'

TD = 5050'