

FORM
2

Rev
12/20

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402862162

Date Received:

02/17/2022

APPLICATION FOR PERMIT TO:

Drill Deepen Re-enter Recomplete and Operate

Amend

Refile

Sidetrack

TYPE OF WELL OIL GAS COALBED OTHER: _____
ZONE TYPE SINGLE ZONE MULTIPLE ZONES COMMINGLE ZONES

Well Name: Flaherty Well Number: 13-7-2
Name of Operator: CONFLUENCE DJ LLC COGCC Operator Number: 10518
Address: 1001 17TH STREET #1250
City: DENVER State: CO Zip: 80202
Contact Name: Brittany Rothe Phone: (303)226-9519 Fax: ()
Email: brothe@confluencelp.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20160056

WELL LOCATION INFORMATION

Surface Location

QtrQtr: SESW Sec: 18 Twp: 4N Rng: 62W Meridian: 6
Footage at Surface: 432 Feet ^{FNL/FSL} FSL 1678 Feet ^{FEL/FWL} FWL
Latitude: 40.306370 Longitude: -104.370540
GPS Data: GPS Quality Value: 1.9 Type of GPS Quality Value: PDOP Date of Measurement: 03/03/2020
Ground Elevation: 4563
Field Name: WATTENBERG Field Number: 90750

Well Plan: is Directional Horizontal (highly deviated) Vertical

If Well plan is Directional or Horizontal attach Deviated Drilling Plan and Directional Data.

Subsurface Locations

Top of Productive Zone (TPZ)

Sec: 13 Twp: 4N Rng: 63W Footage at TPZ: 2354 FNL 470 FEL
Measured Depth of TPZ: 7444 True Vertical Depth of TPZ: 6301 FNL/FSL FEL/FWL

Base of Productive Zone (BPZ)

Sec: 13 Twp: 4N Rng: 63W Footage at BPZ: 2295 FNL 470 FWL
Measured Depth of BPZ: 11850 True Vertical Depth of BPZ: 6301 FNL/FSL FEL/FWL

Bottom Hole Location (BHL)

Sec: 13 Twp: 4N Rng: 63W Footage at BHL: 2295 FNL 470 FWL
FNL/FSL FEL/FWL

LOCAL GOVERNMENT PERMITTING INFORMATION

County: WELD Municipality: N/A

Is the Surface Location of this Well in an area designated as one of State interest and subject to the requirements of § 24-65.1-108 C.R.S.? Yes

Per § 34-60-106(1)(f)(I)(A) C.R.S., the following questions pertain to the Relevant Local Government approval of the siting of the proposed Oil and Gas Location.

SB 19-181 provides that when "applying for a permit to drill," operators must include proof that they sought a local government siting permit and the disposition of that permit application, or that the local government does not have siting regulations. § 34-60-106(1)(f)(I)(A) C.R.S.

Does the Relevant Local Government regulate the siting of Oil and Gas Locations, with respect to this Location? Yes No

If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location.

The disposition of the application filed with the Relevant Local Government is: Approved Date of Final Disposition: 07/20/2018

Comments: The WOGLA was approved on July 20, 2018.

SURFACE AND MINERAL OWNERSHIP AT WELL'S OIL & GAS LOCATION

Surface Owner of the land at this Well's Oil and Gas Location: Fee State Federal Indian

Mineral Owner beneath this Well's Oil and Gas Location: Fee State Federal Indian

Surface Owner Protection Financial Assurance (if applicable): _____ Surety ID Number (if applicable): _____

MINERALS DEVELOPED BY WELL

The ownership of all the minerals that will be developed by this Well is (check all that apply):

- Fee
- State
- Federal
- Indian
- N/A

LEASE INFORMATION

Using standard QtrQtr, Section, Township, Range format describe one entire mineral lease as follows:

- * If this Well is within a unit, describe a lease that will be developed by the Well.
 - * If this Well is not subject to a unit, describe the lease that will be produced by the Well.
- (Attach a Lease Map or Lease Description or Lease if necessary.)

T4N R63W Sec. 13: All

Total Acres in Described Lease: 640 Described Mineral Lease is: Fee State Federal Indian

Federal or State Lease # _____

SAFETY SETBACK INFORMATION

Distance from Well to nearest:

Building: 2511 Feet
 Building Unit: 4071 Feet
 Public Road: 776 Feet
 Above Ground Utility: 712 Feet
 Railroad: 5280 Feet

INSTRUCTIONS:
 - Specify all distances per Rule 308.b.(1).
 - Enter 5280 for distance greater than 1 mile.
 - Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
 - Building Unit – as defined in 100 Series Rules.

Property Line: 432 Feet

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	407-2372	640	T4N R63W Sec.13: All

Federal or State Unit Name (if appl): _____ Unit Number: _____

SUBSURFACE MINERAL SETBACKS

Enter 5280 for distance greater than 1 mile.

Is this Well within a unit? Yes

If YES:

Enter the minimum distance from the Completed Zone of this Well to the Unit Boundary: 470 Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well within the same unit permitted or completed in the same formation: 167 Feet

If NO:

Enter the minimum distance from the Completed Zone of this Well to the Lease Line of the described lease: _____ Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well producing from the same lease and permitted or completed in the same formation: _____ Feet

Exception Location

If this Well requires the approval of a Rule 401.c Exception Location, enter the Rule or spacing order number and attach the Exception Location Request and Waivers. _____

SPACING & FORMATIONS COMMENTS

DRILLING PROGRAM

Proposed Total Measured Depth: 11850 Feet TVD at Proposed Total Measured Depth 6301 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 733 Feet No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No If yes, attach an H₂S Drilling Plan unless a plan was already submitted with the Form 2A per Rule 304.c.(10).

Will there be hydraulic fracture treatment at a depth less than 2,000 feet in this well? No

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: Annular Preventor Double Ram Rotating Head None

Beneficial reuse or land application plan submitted? _____

Reuse Facility ID: _____ or Document Number: _____

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved:  Director of COGCC Date: 4/8/2022

Expiration Date: 04/07/2025

API NUMBER 05 123 47461 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Condition of Approval

<u>COA Type</u>	<u>Description</u>
Drilling/Completion Operations	Per COGCC Order 1-232, Bradenhead tests shall be performed according to the following schedule and Form 17 submitted within 10 days of each test: 1) Within 60 days of rig release, prior to stimulation. If any pressure greater than 200 psi is observed or if there is continuous flow, Operator must contact COGCC engineering for approval prior to stimulation. 2) If a delayed completion, a second test is required between 6-9 months after rig release and must be conducted prior to stimulation. If any pressure greater than 200 psi is observed or if there is continuous flow, Operator must contact COGCC engineering for approval prior to stimulation. 3) A post-production test within 60 days after first sales, as reported on the Form 10, Certificate of Clearance.
Drilling/Completion Operations	1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU (spud notice) for the first well activity with a rig on the pad and provide 48 hour spud notice via Form 42 for all subsequent wells drilled on the pad. 2) Comply with Rule 408.j. and provide cement coverage from TD to a minimum of 500' above Niobrara. Verify coverage with a cement bond log. 3) Oil-based drilling fluid is to be used only after all fresh water aquifers are covered.
Drilling/Completion Operations	If conductors are preset, operator shall comply with Notice to Operators: Procedures for Preset Conductors (dated September 1, 2016).
Drilling/Completion Operations	Operator shall comply with Notice to Operators: Interim Reclamation Procedures for Delayed Operations (dated January 5, 2017).
4 COAs	

Best Management Practices

No	BMP/COA Type	Description
1	Drilling/Completion Operations	Anti-collision: Operator will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within 150 feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators prior to drilling.
2	Drilling/Completion Operations	Logging: The Middlepark 18-21-3L (API No. 05-123-47444-00), well drilled on the pad was logged with an open-hole Resistivity Log and Gamma Ray Log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "No open-hole logs were run. The Middlepark 18-21-3L (API No. 05-123-47444-00) is the well in which open-hole logs were run."

Total: 2 comment(s)

Attachment List

Att Doc Num	Name
402862162	FORM 2 SUBMITTED
402942787	DEVIATED DRILLING PLAN
402942789	DIRECTIONAL DATA
402956095	OffsetWellEvaluations Data
402956113	WELL LOCATION PLAT
403009585	OFFSET WELL EVALUATION

Total Attach: 6 Files

General Comments

User Group	Comment	Comment Date
Permit	SLB has no concerns with this application. Final Review Completed.	03/28/2022
Permit	Emailed the SLB to notify them of this pending application.	03/18/2022
OGLA	The Location and its associated Form 2A materials was fully reviewed during the review of this APD. This APD complies with all COGCC Rules and is adequately protective of public health, safety, welfare, the environment, and wildlife resources. OGLA task passed.	03/02/2022
OGLA	Location lies within 300 feet of a mapped Water of the US. COGCC verified with the operator that the mapped drainage does not have an identifiable Ordinary High Water Mark. Location is in compliance with all COGCC Rules.	03/02/2022

Total: 4 comment(s)