

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203

Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

402992046

Receive Date:

Report taken by:

Site Investigation and Remediation Workplan (Supplemental Form)

This form shall be submitted to the Director for approval prior to the initiation of site investigation and remediation activities. However, this shall not preclude the Operator from taking immediate action to protect public health or safety, the environment, wildlife, or livestock.

This Form 27 describes site conditions as currently understood by the Operator; approval of this Form 27 by COGCC is based on the site conditions accurately described herein; any changes in site conditions identified during or subsequent to the performance of the approved workplan may necessitate additional investigation or remediation which shall be described on a supplemental Form 27. This Form 27 is intended to provide basic information regarding the proposed site investigation and remediation actions, but the workplan may be more fully described in attached documentation.

Closure request is not available for an Initial Site Investigation and Remediation Workplan.

OPERATOR INFORMATION

Name of Operator: <u>PDC ENERGY INC</u>	Operator No: <u>69175</u>	Phone Numbers
Address: <u>1775 SHERMAN STREET - STE 3000</u>		Phone: <u>(303) 860-5800</u>
City: <u>DENVER</u>	State: <u>CO</u>	Zip: <u>80203</u>
Contact Person: <u>Karen Olson</u>	Email: <u>COGCCSpillRemediation@pdce.com</u>	Mobile: <u>()</u>

PROJECT, PURPOSE & SITE INFORMATION

PROJECT INFORMATION

Remediation Project #: 7846 Initial Form 27 Document #: 2145375

PURPOSE INFORMATION

- ☐ Rule 913.c.(1): Pit or Cuttings Trench closure.
- ☐ Rule 913.c.(2): Buried or partially buried vessel closure, which will be by removal.
- ☐ Rule 913.c.(3): Remediation of Spill and Releases pursuant to Rule 912.
- ☐ Rule 913.c.(4): Land treatment of Oily Waste pursuant to Rule 905.e.
- ☐ Rule 913.c.(5): Closure of Centralized E&P Waste Management Facilities pursuant to Rule 907.h.
- ☒ Rule 913.c.(6): Remediation of impacted Groundwater pursuant to Rule 915.e.(3).D, and the contaminant concentrations in Table 915-1.
- ☐ Rule 913.c.(7): Investigation and remediation of natural gas in soil or Groundwater.
- ☐ Rule 913.c.(8): When requested by the Director due to any potential risk to soil, Groundwater, or surface water.
- ☐ Rule 913.c.(9): Decommissioning of Oil and Gas Facilities.
- ☐ Rule 913.g: Changes of Operator.
- ☐ Rule 915.b: Request to leave elevated inorganics in situ.
- ☐ Other: _____

SITE INFORMATION

No Multiple Facilities

Facility Type: <u>LOCATION</u>	Facility ID: <u>305118</u>	API #: _____	County Name: <u>WELD</u>
Facility Name: <u>BARRELL-66N64W 4NENE</u>		Latitude: <u>40.521140</u>	Longitude: <u>-104.548720</u>
		** correct Lat/Long if needed: Latitude: _____	Longitude: _____
QtrQtr: <u>NENE</u>	Sec: <u>4</u>	Twp: <u>6N</u>	Range: <u>64W</u>
		Meridian: <u>6</u>	Sensitive Area? <u>Yes</u>

SITE CONDITIONS

General soil type - USCS Classifications SM

Most Sensitive Adjacent Land Use Agriculture

Is domestic water well within 1/4 mile? Yes

Is surface water within 1/4 mile? Yes

Is groundwater less than 20 feet below ground surface? Yes

Other Potential Receptors within 1/4 mile

Surface water is located approximately 200 feet north of the location. Occupied buildings are located approximately 975 feet west of the location.

SITE INVESTIGATION PLAN**TYPE OF WASTE:**

☒ **E&P Waste** ☐ **Other E&P Waste** ☐ **Non-E&P Waste**

☒ **Produced Water** ☐ **Workover Fluids**

☐ **Oil** ☐ **Tank Bottoms**

☐ **Condensate** ☐ **Pigging Waste**

☐ **Drilling Fluids** ☐ **Rig Wash**

☐ **Drill Cuttings** ☐ **Spent Filters**

☐ **Pit Bottoms**

☐ **Other (as described by EPA)**

DESCRIPTION OF IMPACT

Impacted?	Impacted Media	Extent of Impact	How Determined
Yes	GROUNDWATER	Refer to 4th Qtr 2017 GMA Report	Completion of site investigation plan.
Yes	SOILS	Refer to Figure 1 and Table 1	Completion of site investigation plan.

INITIAL ACTION SUMMARY

Description of initial action or emergency response measures take to abate, investigate, and/or remediate impacts associated with E&P Waste.

A FORM 19 WAS SUBMITTED ON MARCH 25, 2011 AND THE COGCC ASSIGNED SPILL TRACKING NUMBER 2213128 FOR THE SITE. IN ADDITION, PDC SUBMITTED A NO FURTHER ACTION REQUEST TO THE COGCC ON JULY 30, 2012. AN AERIAL MAP OF THE SITE IS INCLUDED AS FIGURE 1.

PROPOSED SAMPLING PLAN**Proposed Soil Sampling**

☒ Will soil samples be collected as part of this investigation? (Number, type (grab/composite), analyses, and locations of samples):

Between September 25, 2015, and November 3, 2017, supplemental site investigation activities were conducted to delineate the remaining petroleum hydrocarbon impacts within the unsaturated interval. 23 soil samples were collected from ten (10) boreholes (BH01-R, SS02A-R, SS02A-R2, and BH03 - BH09) at depths ranging between 22 feet and 34.5 feet below ground surface (bgs). Soil samples were submitted to Summit Scientific for laboratory analysis of benzene, toluene, ethylbenzene, total xylenes (BTEX), naphthalene, total petroleum hydrocarbons (TPH) – gasoline range organics (GRO) by USEPA Method 8260B, and TPH – diesel range organics (DRO) by USEPA Method 8015. Analytical results indicated that TPH concentrations remained in exceedance of regulatory standards below the former 2011 excavation extent between 22 feet and 35 feet bgs. Soil analytical results are summarized in Table 1 and sample locations are illustrated in Figure 1.

Proposed Groundwater Sampling

☒ Will groundwater samples be collected as part of this investigation? (Number, analyses, and locations of samples):

During supplemental site investigations, groundwater was encountered at approximately 36 feet bgs. Temporary monitoring wells were installed in each borehole for monitoring and remediation purposes. Groundwater samples were collected from 8 monitoring wells (SS02A-R2, and BH03 – BH09) and submitted for laboratory analysis of benzene, toluene, ethylbenzene, and total xylenes (BTEX) by USEPA Method 8260B. Analytical results indicated that benzene concentrations were above the applicable COGCC Table 910-1 standard in sample location SS02A-R2.

Proposed Surface Water Sampling

☐ Will surface water samples be collected as part of this investigation? (Number, analyses, and locations of samples):

Additional Investigative Actions

☐ Additional alternative investigative actions described in attached Site Investigation Plan (summary):

SITE INVESTIGATION REPORT

SAMPLE SUMMARY

Soil

Number of soil samples collected 23
Number of soil samples exceeding 915-1 6
Was the areal and vertical extent of soil contamination delineated? Yes
Approximate areal extent (square feet) 200

NA / ND

-- Highest concentration of TPH (mg/kg) 2760
NA Highest concentration of SAR
BTEX > 915-1 No
Vertical Extent > 915-1 (in feet) 35

Groundwater

Number of groundwater samples collected 8
Was extent of groundwater contaminated delineated? Yes
Depth to groundwater (below ground surface, in feet) 36'
Number of groundwater monitoring wells installed 7
Number of groundwater samples exceeding 915-1 1

-- Highest concentration of Benzene (µg/l) 120
-- Highest concentration of Toluene (µg/l) 150
-- Highest concentration of Ethylbenzene (µg/l) 120
-- Highest concentration of Xylene (µg/l) 1200
NA Highest concentration of Methane (mg/l)

Surface Water

0 Number of surface water samples collected
 Number of surface water samples exceeding 915-1
If surface water is impacted, other agency notification may be required.

OTHER INVESTIGATION INFORMATION

☐ Were impacts to adjacent property or offsite impacts identified?

☐ Were background samples collected as part of this site investigation?

☐ Was investigation derived waste (IDW) generated as part of this investigation?

Volume of solid waste (cubic yards) Volume of liquid waste (barrels)

☒ Is further site investigation required?

Based on the fourth quarter 2019 groundwater analytical data, three (3) monitoring wells will be installed south of the existing monitoring well network to establish down-gradient point of compliance.

REMEDIAL ACTION PLAN

Does this Supplemental Form 27A include changes to a previously approved Remedial Action Plan? No

SOURCE REMOVAL SUMMARY

Describe how source is to be removed.

The source area was previously excavated and impacted material was transported off-site, as described in the Form 19 submitted on March 25, 2011.

REMEDIATION SUMMARY

Describe how remediation of existing impacts to soil and groundwater is to be accomplished (i.e. summarize remedial action plan). Provide a brief narrative description including: technical justification, schedule for implementation, estimated time to attain NFA status, plus plans and specifications for the selected remedial action technology.

Monitored natural attenuation (MNA) was selected as the remediation strategy for this site during the fourth quarter 2017 and will remain as the selected remediation strategy through the second quarter 2022.

Soil Remediation Summary

☐ In Situ

_____ Bioremediation (or enhanced bioremediation)
_____ Chemical oxidation
_____ Air sparge / Soil vapor extraction
_____ Natural Attenuation
_____ Other _____

☐ Ex Situ

_____ Excavate and offsite disposal
_____ If Yes: Estimated Volume (Cubic Yards) _____
_____ Name of Licensed Disposal Facility or COGCC Facility ID # _____
_____ Excavate and onsite remediation
_____ Land Treatment
_____ Bioremediation (or enhanced bioremediation)
_____ Chemical oxidation
_____ Other _____

Groundwater Remediation Summary

_____ Bioremediation (or enhanced bioremediation)
_____ Chemical oxidation
_____ Air sparge / Soil vapor extraction
Yes _____ Natural Attenuation
_____ Other _____

GROUNDWATER MONITORING

If groundwater has been impacted, describe proposed monitoring plan, including # of wells or sample points, monitoring schedule, analytical methods, points of compliance. Attach a groundwater monitoring location diagram.

Groundwater monitoring will continue on a quarterly basis at the 15 site monitoring wells (SS02RA, and BH03-BH16) until closure criteria are met. Groundwater samples will be submitted for laboratory analysis of benzene, toluene, ethylbenzene, total xylenes (BTEX), naphthalene, 1,2,4-trimethylbenzene, and 1,3,5-trimethylbenzene by EPA Method 8260B, and chloride anions by EPA Method 300.0 in accordance with Table 915-1. Analytical results indicated that organic compound concentrations and inorganic parameters were in compliance with the applicable COGCC Table 915-1 regulatory standards in all monitoring well locations. Additionally, the first quarter 2022 marks the fourth consecutive quarter that TDS and sulfate anions were in compliance with the applicable regulatory standards.

REMEDIATION PROGRESS UPDATE

PERIODIC REPORTING

Approved Reporting Schedule:

☒ Quarterly

☐ Semi-Annually

☐ Annually

☐ Other

☐ **Request Alternative Reporting Schedule:**

☐ Semi-Annually

☐ Annually

☐ Other

Rule 913.e:

After initial approval of a Form 27, the Operator will provide quarterly update reports in a Supplemental Form 27 to document progress of site investigation and remediation, unless an alternative reporting schedule has been requested by the Operator and approved by the Director. The Director may request a more frequent reporting schedule based on site-specific conditions.

Report Type:

☒ Groundwater Monitoring

☐ Land Treatment Progress Report

☐ O&M Report

☐ Other

WASTE DISPOSAL INFORMATION

Was E&P waste generated as part of this remediation?

Describe beneficial use, if any, of E&P Waste derived from this remediation project:

Volume of E&P Waste (solid) in cubic yards

E&P waste (solid) description

COGCC Disposal Facility ID #, if applicable:

Non-COGCC Disposal Facility:

Volume of E&P Waste (liquid) in barrels

E&P waste (liquid) description

COGCC Disposal Facility ID #, if applicable:

Non-COGCC Disposal Facility:

REMEDIATION COMPLETION REPORT

REMEDIATION COMPLETION SUMMARY

Is this a Final Closure Request for this Remediation Project? No

If YES:

☐ Compliant with Rule 913.h.(1).

☐ Compliant with Rule 913.h.(2).

☐ Compliant with Rule 913.h.(3).

Do all soils meet Table 915-1 standards?

Does the previous reply indicate consideration of background concentrations?

Does Groundwater meet Table 915-1 standards?

Is additional groundwater monitoring to be conducted?

Operator shall comply with the COGCC 1000-Series Reclamation Requirements for all impacted and disturbed areas.

RECLAMATION PLAN

RECLAMATION PLANNING

Describe reclamation plan. Discuss existing and new grade recontouring; method and testing of compaction alleviation; and reseeding program, including location of new seed, seed mix and noxious weed prevention. Attach diagram or drawing.

The excavation was backfilled and re-graded to match pre-existing conditions. The production facility remains operational. Following decommissioning of this facility, the location will be reclaimed in accordance with the COGCC 1000 series.

Is the described reclamation complete? _____

Does the reclamation described herein constitute interim or final reclamation of the Oil and Gas Location?

☐ Interim ☐ Final

Did the Surface Owner provide the seed mix? _____

If YES, does the seed mix comply with local soil conservation district recommendations? _____

Did the local soil conservation district provide the seed mix? _____

SITE RECLAMATION DATES

Proposed date of commencement of Reclamation. _____

Proposed date of completion of Reclamation. _____

IMPLEMENTATION SCHEDULE

Per Rule 913.d.(2): Any change from the approved implementation schedule will be requested at least 14 days in advance, and the Operator may not make the change without the Director's approval.

PRIOR DATES

Date of Surface Owner notification/consultation, if required. 02/10/2011

Actual Spill or Release date, or date of discovery. 02/10/2021

SITE INVESTIGATION DATES

Date of Initial Actions described in Site Investigation Plan (start date). _____

Proposed site investigation commencement. 02/10/2011

Proposed completion of site investigation. 01/09/2020

REMEDIAL ACTION DATES

Proposed start date of Remediation. 04/18/2012

Proposed date of completion of Remediation. 12/13/2026

Per Rule 913.d.(2): Any change from the approved implementation schedule will be requested at least 14 days in advance, and the Operator may not make the change without the Director's approval.

☐ Change from approved implementation schedule per Rule 913.d.(2).

Basis for change in implementation schedule:

OPERATOR COMMENT

This Supplemental Form 27 was submitted to summarize quarterly groundwater monitoring activities and analytical results collected during the first quarter 2022 at the Barrell 41-4 tank battery location.

Analytical results indicated that organic compound concentrations and inorganic parameters were in compliance with the applicable COGCC Table 915-1 regulatory standards in all monitoring well locations. Additionally, the first quarter 2022 marks the fourth consecutive quarter that TDS and sulfate anions were in compliance with the applicable regulatory standards. Based on these results, PDC is requesting that TDS and sulfate anion analysis is removed from the quarterly sampling plan.

I hereby certify all statements made in this form are to the best of my knowledge true, correct, and complete.

Signed: Karen Olson

Title: Senior Program Manager

Submit Date:

Email: COGCCSpillRemediation@pdce.com

Based on the information provided herein, this Application for Site Investigation and Remediation Workplan complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:

Date:

Remediation Project Number: 7846

COA Type**Description**

--	--

Attachment Check List

Upon approval, the approved Form 27 and all listed attachments will be indexed to the Remediation Project file. Only the approved Form 27 will also be indexed to the related Facilities.

Att Doc Num**Name**

403014598	MONITORING REPORT
-----------	-------------------

Total Attach: 1 Files

General Comments**User Group****Comment****Comment Date**

		Stamp Upon Approval
--	--	---------------------

Total: 0 comment(s)