



414503

Rig # 807-Milliken

Cement Ticket

Customer Name	Date Of Service:
Noble Energy	4/4/2022

Location	County	Equipment
Alexander #33-02	Weld County, CO	C1003

Billing

Description	Qty	Rate	Total
P and A Charge(Each)			
Mileage(Miles)			
G Cement(Bags)			
Data Acquisition(Each)			
Iron Inspection(Each)			
Sugar(Lbs)			
Water Delivery(Barrels)			

Description	Qty	Rate	Total
Miscellaneous			
Miscellaneous			
Miscellaneous			
Miscellaneous			

defoamer
retarder
rigless P&A
charge
water bobtail
hours

Description of Work	Start Time 11:00 am	Stop Time 06:00 pm
----------------------------	----------------------------	---------------------------

UWRWE-A2409-ABN Gate to gate: 11:00 am – 5:00 pm MOB to location, spot in, rig up, flowback incinerated gas, Status: 2-3/8" 4.7# tubing cut at 6,723' inside 4-1/2" 15.1# casing, pump down tubing, pumped 30 bbl. water, pumped 5 bbl. LCM pill, displaced with 25.2 bbl. waited 30 minutes, established circulation with 47 bbl. of water, pumped 67 bbl. additional water, pumped 5 bbl. freshwater spacer, mix and pumped 35 sxs of 15.8# 1.15 cu.ft./sack Class G cement with retarder, 7.2 bbl. of slurry, displaced with 24.7 bbl. to cover from 6,723' to 6,210', RD valve, wash out pump, RD equipment, MOB to shop Non rev: post trip, clean and drain truck, load cement

Payroll Section					
Employee	Rev Hrs.	Travel Hrs.	Non Rev Hrs.	Total	
Supervisor	Rascon, Aron	0.00	0.00	0.00	0.00
Operator	Pena, Marcos	6.00	0.00	1.00	7.00
Derrick	Retana Portillo, Gerardo	6.00	0.00	1.00	7.00
FloorHand	Meza, Abraham	6.00	0.00	1.00	7.00

No UnReported Incidents Per My Signature

Ranger Tool Pusher

Customer/Agent: