



417964

Rig # 807-Milliken

### Cement Ticket

<b>Customer Name</b>	<b>Date Of Service:</b>
Chevron	4/20/2022

<b>Location</b>	<b>County</b>	<b>AFE</b>	<b>Equipment</b>
McMillen G19-19	Weld County, CO		C1002

#### Billing

Description	Qty	Rate	Total
P and A Charge(Each)			
Mileage(Miles)			
G Cement(Bags)			
Data Acquisition(Each)			
Iron Inspection(Each)			
Sugar(Lbs)			
Water Delivery(Barrels)			

Description	Qty	Rate	Total
Miscellaneous			
Miscellaneous			
Miscellaneous			
Miscellaneous			

defoamer  
retarder  
rigless P&A  
charge  
water bobtail  
hours

<b>Description of Work</b>	<b>Start Time</b> 05:00 am	<b>Stop Time</b> 11:30 am
----------------------------	----------------------------	---------------------------

UWRWE-A2465-ABN Patricia Albidrez Gate to gate: 6:00 am – 11:30 am MOB to location, spot in, rig up, flowback incinerated gas, Status: 2-3/8" 4.7# tubing cut at 6,884' inside 4 -1/2" 11.6# casing, pump down tubing, pump 30 bbl. freshwater, pumped 4 bbl. LCM pill, displaced with 25.8 bbl. waited 15 minutes, pump 10 bbl., waited 15 minutes, established circulation with 39 bbl. of water, pumped 145 bbl. total water, pumped 5 bbl. freshwater spacer, mix and pumped 35 sxs of 15.8# 1.15 cu.ft./sack Class G cement with retarder, 7.2 bbl. of slurry, displaced with 25.3 bbl. to cover from 6,884' to 6,371', RD valve, wash out pump, RD equipment, MOB to next location Non rev: post trip truck, loaded cement

Payroll Section					
Employee	Rev Hrs.	Travel Hrs.	Non Rev Hrs.	Total	
Supervisor	Rascon, Aron	0.00	0.00	0.00	0.00
Operator	Pena, Marcos	5.50	0.00	2.50	8.00
Derrick	Held, Robert	5.50	0.00	1.50	7.00
FloorHand	Meza, Abraham	5.50	0.00	1.00	6.50

No UnReported Incidents Per My Signature

Ranger Tool Pusher

Customer/Agent: