

FORM
5A

Rev
09/20

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

403053911

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 96850

2. Name of Operator: TEP ROCKY MOUNTAIN LLC

3. Address: 1058 COUNTY ROAD 215

City: PARACHUTE State: CO Zip: 81635

4. Contact Name: Jeff Kirtland

Phone: (970) 263-2736

Fax:

Email: jkirtland@terraep.com

5. API Number 05-045-24401-00

7. Well Name: FEDERAL

8. Location: QtrQtr: NESE Section: 9 Township: 6S Range: 94W Meridian: 6

9. Field Name: RULISON Field Code: 75400

6. County: GARFIELD

Well Number: RWF 332-9

Completed Interval

FORMATION: WILLIAMS FK-ROLLINS-CAMEO Status: PRODUCING Treatment Type: HYDRAULIC FRACTURING

Treatment Date: 03/26/2022 End Date: 04/06/2022 Date this Formation was Completed: 05/04/2022

Perforations Top: 6073 Bottom: 9561 No. Holes: 432 Hole size: 35/100 Open Hole: ☐

Describe the Formation Treatment, including the following: type of fluid used (gel, slickwater, etc.), type and concentration of acid used (HCl, HF, etc.), types and amounts of proppant(s) used, depth details of multiple zones, and method used to determine flowback volume.

176,698 BBLs of Slickwater; 6,035 gals of Biocide; 1,741,375 lbs of Proppant

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 176842 Max pressure during treatment (psi): 7452

Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment: Min frac gradient (psi/ft): 0.73

Total acid used in treatment (bbl): 0 Number of staged intervals: 18

Recycled or Reused Fluids used in treatment (bbl): 176698 Flowback volume recovered (bbl): 47673

Fresh water used in treatment (bbl): 144 Disposition method for flowback: RECYCLE

Total proppant used (lbs): 1741375

Fracture stimulations must be reported on [FracFocus.org](https://www.fracturefocus.org)

Test Information:

05/04/2022 Hours: 24 Bbl oil: 0 Mcf Gas: 4247 Bbl H2O: 0
Date Calculated 24 hour rate: Bbl oil: 0 Mcf Gas: 4247 Bbl H2O: 0 GOR: 0
Test Method: Flowing Casing PSI: 1880 Tubing PSI: 1730 Choke Size: 24/64
Gas Disposition: SOLD Gas Type: DRY Btu Gas: 1137 API Gravity Oil: 0
Tubing Size: 2 + 3/8 Tubing Setting Depth: 9197 Tbg setting date: 04/09/2022 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Print Name: Ashley Noonan

Title: Sr Regulatory Analyst Date: Email: anoonan@terraep.com

Attachment List

Att Doc Num Name

403058385 WELLBORE DIAGRAM

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)