



421779

Rig # 807-Milliken

Cement Ticket

<b>Customer Name</b>	<b>Date Of Service:</b>
Chevron	5/4/2022

<b>Location</b>	<b>County</b>	<b>AFE</b>	<b>Equipment</b>
Bell #41-29	Weld County, CO		C1003

Billing

Description	Qty	Rate	Total
P and A Charge(Each)			
Mileage(Miles)			
G Cement(Bags)			
Data Acquisition(Each)			
Iron Inspection(Each)			
Sugar(Lbs)			
Water Delivery(Barrels)			

Description	Qty	Rate	Total
Miscellaneous			Cement above 35 sxs
Miscellaneous			defoamer
Miscellaneous			retarder
Miscellaneous			rigless P&A charge
Miscellaneous			water bobtail hours
Miscellaneous			wireline credit for lack of tubing cut need

<b>Description of Work</b>	<b>Start Time</b> 05:00 am	<b>Stop Time</b> 01:30 pm
----------------------------	----------------------------	---------------------------

UWRWE-A2429-ABN Patricia Albidrez Gate to gate: 6:00 am –1:30 pm MOB to location, spot in, rig up, flowback incinerated gas, Status: 2-3/8" 4.7# tubing cut at 7,554' inside 4-1/2" 11.6# casing, pump down tubing, pump 35 bbl. freshwater, pumped 5 bbl. LCM pill, displaced with 28.4 bbl. waited 15 minutes, pump 3 bbl., waited 15 minutes, established circulation with 86 bbl. of water, pumped 160 bbl. total water, pumped 5 bbl. freshwater spacer, mix and pumped 65 sxs of 15.8# 1.15 cu.ft./sack Class G cement with retarder, 13.3 bbl. of slurry, displaced with 26.2 bbl. to cover from 7,554' to 6,601', RD valve, wash out pump, RD equipment Non rev: pretrip truck, post trip truck

Payroll Section					
Employee		Rev Hrs.	Travel Hrs.	Non Rev Hrs.	Total
Supervisor	Rascon, Aron	0.00	0.00	0.00	0.00
Operator	Pena, Marcos	7.50	0.00	1.00	8.50
Derrick	Held, Robert	7.50	0.00	1.00	8.50
FloorHand	Meza, Abraham	7.50	0.00	1.00	8.50

No UnReported Incidents Per My Signature

Ranger Tool Pusher

Customer/Agent: