

FORM
2

Rev
05/22

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

403022611

(SUBMITTED)

Date Received:

06/15/2022

APPLICATION FOR PERMIT TO

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

Amend ☒

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER: _____

Refill ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: Regina Well Number: 7-66-3-10-6N
Name of Operator: ENERPLUS RESOURCES (USA) CORPORATION COGCC Operator Number: 10177
Address: 950 17TH STREET #2200
City: DENVER State: CO Zip: 80202
Contact Name: Jacob Everhart Phone: (720)2796743 Fax: ()
Email: jeverhart@enerplus.com

FINANCIAL ASSURANCE FOR PLUGGING, ABANDONMENT, AND RECLAMATION

COGCC Financial Assurance

☐ The Operator has provided or will provide Financial Assurance to the COGCC for this Well.

Surety ID Number (if applicable): 20170023

Federal Financial Assurance

☐ In checking this box, the Operator certifies that it has provided or will provide at least this amount of Financial Assurance to the federal government for this Well. (Per Rule702.a.)

Amount of Federal Financial Assurance \$ _____

WELL LOCATION INFORMATION

Surface Location

QtrQtr: SESE Sec: 34 Twp: 8N Rng: 66W Meridian: 6

FNL/FSL

FEL/FWL

Footage at Surface: 471 Feet FSL 1237 Feet FEL

Latitude: 40.612663 Longitude: -104.758366

GPS Data: GPS Quality Value: 1.6 Type of GPS Quality Value: PDOP Date of Measurement: 10/23/2019

Ground Elevation: 4996

Field Name: WATTENBERG Field Number: 90750

Well Plan: is ☐ Directional ☒ Horizontal (highly deviated) ☐ Vertical

If Well plan is Directional or Horizontal attach Deviated Drilling Plan and Directional Data.

Subsurface Locations

Top of Productive Zone (TPZ)

Sec: 3 Twp: 7N Rng: 66W Footage at TPZ: 500 FNL 500 FWL
Measured Depth of TPZ: 8791 True Vertical Depth of TPZ: 7375 FNL/FSL FEL/FWL

Base of Productive Zone (BPZ)Sec: 10 Twp: 7N Rng: 66WFootage at BPZ: 500 FSL 500 FWLMeasured Depth of BPZ: 18273True Vertical Depth of BPZ: 7375 FNL/FSL FEL/FWL**Bottom Hole Location (BHL)**Sec: 10 Twp: 7N Rng: 66WFootage at BHL: 500 FSL 500 FWL

FNL/FSL

FEL/FWL

LOCAL GOVERNMENT PERMITTING INFORMATIONCounty: WELDMunicipality: N/A

Is the Surface Location of this Well in an area designated as one of State interest and subject to the requirements of § 24-65.1-108 C.R.S.? Yes

Per § 34-60-106(1)(f)(I)(A) C.R.S., the following questions pertain to the Relevant Local Government approval of the siting of the proposed Oil and Gas Location.

SB 19-181 provides that when "applying for a permit to drill," operators must include proof that they sought a local government siting permit and the disposition of that permit application, or that the local government does not have siting regulations. § 34-60-106(1)(f)(I) (A) C.R.S.

Does the Relevant Local Government regulate the siting of Oil and Gas Locations, with respect to this Location? ☒ Yes ☐ No

☒ If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location.

The disposition of the application filed with the Relevant Local Government is: Approved Date of Final Disposition: 09/18/2019

Comments: WOGLA Approved 09/18/2019. WOGLA19-0182

SURFACE AND MINERAL OWNERSHIP AT WELL'S OIL & GAS LOCATION

Surface Owner of the land at this Well's Oil and Gas Location: ☒ Fee ☐ State ☐ Federal ☐ Indian

Mineral Owner beneath this Well's Oil and Gas Location: ☒ Fee ☐ State ☐ Federal ☐ Indian

Surface Owner Protection Bond (if applicable): _____

Surety ID Number (if applicable): _____

MINERALS DEVELOPED BY WELL

The ownership of all the minerals that will be developed by this Well is (check all that apply):

☒ Fee☐ State☐ Federal☐ Indian☐ N/A**LEASE INFORMATION**

Using standard QtrQtr, Section, Township, Range format describe one entire mineral lease as follows:

* If this Well is within a unit, describe a lease that will be developed by the Well.

* If this Well is not subject to a unit, describe the lease that will be produced by the Well.

(Attach a Lease Map or Lease Description or Lease if necessary.)

Township 7 North, Range 66W, 6th PM Section 3: SW

Total Acres in Described Lease: 160 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

SAFETY SETBACK INFORMATION

Distance from Well to nearest:

Building: 384 Feet
Building Unit: 805 Feet
Public Road: 458 Feet
Above Ground Utility: 444 Feet
Railroad: 5280 Feet
Property Line: 471 Feet

INSTRUCTIONS:

- Specify all distances per Rule 308.b.(1).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit – as defined in 100 Series Rules.

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	407-1782	1280	Sec 3 & 10: All

Federal or State Unit Name (if appl):

Unit Number:

SUBSURFACE MINERAL SETBACKS

Enter 5280 for distance greater than 1 mile.

Is this Well within a unit? Yes

If YES:

Enter the minimum distance from the Completed Zone of this Well to the Unit Boundary: 500 Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well within the same unit permitted or completed in the same formation: 332 Feet

If NO:

Enter the minimum distance from the Completed Zone of this Well to the Lease Line of the described lease: Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well producing from the same lease and permitted or completed in the same formation: Feet

Exception Location

- ☐ If this Well requires the approval of a Rule 401.c Exception Location, enter the Rule or spacing order number and attach the Exception Location Request and Waivers.

SPACING & FORMATIONS COMMENTS

DRILLING PROGRAM

Proposed Total Measured Depth: 18273 Feet

TVD at Proposed Total Measured Depth 7375 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 315 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than

or equal to 100 ppm? No If yes, attach an H₂S Drilling Plan unless a plan was already submitted with the Form 2A per Rule 304.c.(10).

Will there be hydraulic fracture treatment at a depth less than 2,000 feet in this well? No

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: 450526 or Document Number:

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	J-55	65	0	80	179	80	0
SURF	13+1/2	9+5/8	J-55	36	0	1500	304	1500	0
1ST	8+1/2	5+1/2	P-110	20	0	18273	2724	18273	

☐ Conductor Casing is NOT planned

POTENTIAL FLOW AND CONFINING FORMATIONS

Zone Type	Formation /Hazard	Top M.D.	Top T.V.D.	Bottom M.D.	Bottom T.V.D.	TDS (mg/L)	Data Source	Comment
Groundwater	Fox Hills	0	0	1687	1687	501-1000	USGS	
Confining Layer	Pierre Shale	1687	1687	4201	3985			
Groundwater	Parkman	4201	3985	4600	4302	1001-10000	Other	DWLS formation water catalog
Confining Layer	Pierre Shale	4600	4302	5732	5199			
Groundwater	Shannon	5732	5199	5900	5325	1001-10000	Other	DWLS formation water catalog
Confining Layer	Pierre Shale	5900	5325	8332	7234			
Confining Layer	Sharon Springs	8332	7234	8368	7254			
Hydrocarbon	Niobrara	8368	7254	18273	7375			Bottom TVD is bottom of the well and not bottom of the formation; the formation is not planned to be exited.

The subreport 'Submit' could not be found at the specified location W:\Inetpub\Net\Reports\Form2\02_Submit_T.rpt. Please verify the path.

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

--	--

Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Drilling/Completion Operations	Multi Well Open-Hole Logging - Rule 317.p: Alternative Logging Program: One of the first wells drilled on the pad – Lloydminster 7-66-3-10-2N (API 05-123-46142). The first well drilled on this pad has been logged with open-hole Resistivity Log and Gamma Ray Log from the kick-off point into the surface casing. That info is attached to form 5 Doc# 402673978. All proposed wells related to this permit will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open hole logs shall clearly state “No open-hole logs were run” and shall clearly identify the well (Lloydminster 7-66-3-10-2N (API 05-123-46142)) in which open-hole logs were run.

Total: 1 comment(s)

Attachment List

<u>Att Doc Num</u>	<u>Name</u>
403079730	WELL LOCATION PLAT
403079732	DEVIATED DRILLING PLAN
403079736	DIRECTIONAL DATA
403080091	OffsetWellEvaluations Data

Total Attach: 4 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)

Public Comments

No public comments were received on this application during the comment period.

