

FEDERAL PERRY #13-32 EXISTING WBD



DESCRIPTION DEPTH WELLBORE

10 sks surfce plug 30'

8-5/8" Surface Casing:
(cement to surface) 173'

153'
20 sks plug across shoe
193'

7-7/8" Production Hole: 6,680'

WELL: FEDERAL PERRY #13-32

LOCATION: SWSW 32 9N 58W
640FSL 621 FWL (Planned)
40.701811°N, -103.895020°E

FORMATION: DSND 1988

API #: 05-123-13640

Field: Wildcat

CURRENT STATUS: DA

Spud: 11/15/87
Plug: 11/21/1987

Type	Size	Weight	Top	Bottom	Hole Size
Surface	8-5/8"	24.0 ppf	0	173'	12-1/4"
Top Production	None		0	6,680'	7-7/8"

Elevation Data		
GL	4852	feet
KB	4862	feet
Difference	10	feet

Formation Tops Data		
Formation	Depth	
Base of Fox Hills	383'	MD
Base of Upper Pierre	1203'	MD
Niobrara	5762'	MD
Fort Hays	6008'	MD
Codell	6058'	MD
D Sand	6505'	MD
J Sand	6590'	MD