



Cement Ticket

Customer Name Chevron	Date Of Service: 6/2/2022
---------------------------------	-------------------------------------

Location Klein #12-01	County Weld County, CO	AFE	Equipment C1003
---------------------------------	----------------------------------	------------	---------------------------

Billing			
Description	Qty	Rate	Total
P and A Charge(Each)			
Mileage(Miles)			
G Cement(Bags)			
Data Acquisition(Each)			
Iron Inspection(Each)			
Sugar(Lbs)			
Water Delivery(Barrels)			
Description			
Miscellaneous			defoamer
Miscellaneous			retarder
Miscellaneous			rigless P&A charge
Miscellaneous			water bobta hours
Miscellaneous			wireline gauge ring charge

Description of Work	Start Time 05:00 am	Stop Time 02:00 pm
----------------------------	----------------------------	---------------------------

UWRWE-A2558-ABN Patricia Albidrez Gate to gate: 6:00 am – 2:00 pm MOB to location, spot in, rig up, flowback incinerated gas, Status: 2-3/8" 4.7# tubing cut at 6,749' inside 4-1/2" 11.6# casing, pump down tubing, pump 30 bbl. freshwater, pumped 7 bbl. LCM pill, displaced with 25.3 bbl. waited 30 minutes, established circulation with 58 bbl. of water, pumped 138 bbl. total water, pumped 5 bbl. freshwater spacer, mix and pumped 35 sxs of 15.8# 1.15 cu.ft./sack Class G cement mix with retarder, 7.2 bbl. of slurry, displaced with 24.7 bbl. to cover from 6,749' to 6,236', RD valve, wash out pump, RD equipment Non rev: pretrip truck, prep for job

Payroll Section					
Employee	Rev Hrs.	Travel Hrs.	Non Rev Hrs.	Total	
Supervisor Rascon, Aron	0.00	0.00	0.00	0.00	0.00
Operator Pena, Marcos	9.00	0.00	0.00	0.00	9.00
Derrick Meza, Abraham	9.00	0.00	0.00	0.00	9.00

No Unreported Incidents Per My Signature

 Ranger Tool Pusher

 Customer/Agent: