



**Cement Ticket**

<b>Customer Name</b> Chevron	<b>Date Of Service:</b> 6/9/2022
---------------------------------	-------------------------------------

<b>Location</b> Steve J18-23	<b>County</b> Weld County, CO	<b>AFE</b>	<b>Equipment</b> C1003
---------------------------------	----------------------------------	------------	---------------------------

Billing			
Description	Qty	Rate	Total
P and A Charge(Each)			
Mileage(Miles)			
G Cement(Bags)			
Data Acquisition(Each)			
Iron Inspection(Each)			
Sugar(Lbs)			
Water Delivery(Barrels)			
<b>Description</b>			
Miscellaneous			defoamer
Miscellaneous			retarder
Miscellaneous			rigless P&/ charge
Miscellaneous			water bobt: hours
Miscellaneous			Wireline credit (tubi already at depth)

<b>Description of Work</b>	<b>Start Time</b> 05:00 am	<b>Stop Time</b> 05:00 pm
----------------------------	----------------------------	---------------------------

UWRWE-A2596-ABN Patricia Albidrez Gate to gate: 6:00 am – 5:00 pm MOB to location, spot in, rig up, flowback incinerated gas, Status: 2-3/8" 4.7# tubing cut at 7,746' inside 4-1/2" 11.6# casing, pump down tubing, pump 35 bbl. freshwater, pumped 1 bbl. LCM pill, displaced with 29.1 bbl. waited 30 minutes, established circulation with 53 bbl. of water, pumped 120 bbl. total water, pumped 5 bbl. freshwater spacer, mix and pumped 35 sxs of 15.8# 1.15 cu.ft./sack Class G cement with retarder, 7.2 bbl. of slurry, displaced with 28.6 bbl. to cover from 7,746' to 7,233', RD valve, wash out pump, RD equipment Non rev: pretrip truck, prep for job

Payroll Section						
Employee	Rev Hrs.	Travel Hrs.	Non Rev Hrs.	Total		
Supervisor Rascon, Aron	0.00	0.00	0.00	0.00	0.00	
Operator Pena, Marcos	11.00	0.00	1.00	12.00	12.00	
Derrick Meza, Abraham	11.00	0.00	1.00	12.00	12.00	

No UnReported Incidents Per My Signature

\_\_\_\_\_  
 Ranger Tool Pusher

\_\_\_\_\_  
 Customer/Agent: