

**Equity Oil & Gas
Emerald "C" 133
API # 103-05456**

3' of Cement		<u>10-3/4" Csg set @ 20' to surface</u>
146' Cement plug		Plug #4 Class ASTM C Cement 150' to 4' from surface 112 Sacks
150' Rock & shale plug		Plug #3 Shale & rock plug 350' to 150'
150' Cement plug		Plug #2 Class ASTM C Cement 500' to 350' 120 sacks
120' Rock & shale plug		Plug #1 Shale & rock mix 620' to 500'
<u>Sludge/Oil TD@525</u> TD @ 620' Thick mud and oil		620' Sludge, rock, and mud bridged off (Unable to get to bottom)
		<u>Surface</u> Open hole to Approx: 620' Open hole size 12" to 16"