

Well: Lukie-Do 2-24

API:05-099-06889

Operator: Cholla Petroleum Inc

County: Prowers

State: Colorado

Field: Channing North

Location: SWNW 24 21S 47W

SHL: 1500' FNL 660 FWL

Elevation: 3832' GR 3841' KB

Spud Date: 7/12/2006

TD Date: 7/26/2006

Log Tops

Morrow 4698'

**Surface Casing and Cement**  
Casing size: 8 5/8", Hole Size: 12 1/4", Weight:  
landed @ 1046',cemented with 500 sxs  
TOC @ Surface

**Main Hole**  
7-7/8" to TD

**Production Casing and Cement**  
Casing size: 4 1/2", Hole size: 7 7/8", Weight:  
landed @ 4894',cemented with 250 sxs  
TOC 3724'

**Production Tubing**  
2 3/8" tubing, set @  
4685'

Perf'd the Morrow @ 4694' - 4714' (80 holes)

4900' — Driller's TD

