

PROPOSED WELL(S)											
Surface Location			Surface Location			Surface Location			Surface Location		
Well Name and Number			Well Name and Number			Well Name and Number			Well Name and Number		
Bunker 8-1H			Bunker 8-4H			Bunker 8-7H			Bunker 8-9H		
Bunker 8-2H			Bunker 8-5H			Bunker 8-8H			Bunker 8-9H		
Bunker 8-3H			Bunker 8-6H			Bunker 8-9H			Bunker 8-9H		
Operator's Wellbore Integrity Contact: Neil Warner											
OFFSET WELL EVALUATIONS											
Offset Well API #	Offset Well Name	Shortest Horizontal Distance from Offset Well to any Proposed HZ Well	Offset Well Operator	Offset Well Spud Date	Offset Well Status	Offset Well Surface Casing Setting Depth	Depth of Deepest WaterWell or Base of Fox Hills (DJ)	Offset Well Top of Production Casing Cement	Most Recent Surface Casing Pressure Reported (psig)		Required Comments
05-069-05044	BUNKER #1	1,079'	PEASE OIL & BIG HORN	02/08/64	PA	202'	62'	4,348'	N/A		No Remediation - Abandoned 9/8/97, Never Perforated in the Nio or Cdl
05-069-05045	BUNKER #2	1,088'	EXTRACTION	06/17/64	PA	191'	62'	4,198'	N/A		No Remediation - Abandoned 4/22/69, TOC in pipe @ 4,150'
05-069-05046	SKAER FARM #1	1,586'		09/12/64	PA	230'		3,875'	N/A		No Remediation - Abandoned 05/11/2015, TOC in pipe @ 4144', 1220', 80', 0'
05-069-05048	Saulcy 1	333'	Magpie	02/15/66	PR	232'		3,870'	0		Option 4 - 5K Wellhead and Monitor Pressure
05-069-05049	Bunker 5	153'	Magpie	09/21/55	PR	270'		3,859'	0		Option 4 - 5K Wellhead and Monitor Pressure
05-069-05050	Bunker 6	187'	Magpie	10/25/63	PR	207'		4,014'	0		Option 4 - 5K Wellhead and Monitor Pressure
05-069-05051	Trindle 3	178'	Magpie	10/05/63	PR	193'		3,952'	18		Option 4 - 5K Wellhead and Monitor Pressure
05-069-05052	Trindle 1	192'	Magpie	10/13/61	PR	346'		3,732'	0		Option 4 - 5K Wellhead and Monitor Pressure
05-069-05053	Gregg 1	137'	Skaer	08/11/50	PA	86'		0'	N/A		No Remediation - Shallow Offset @ 1490' MD
05-069-05055	Lavington-Atkinson Trindle 2	105'	Lakota Petr	10/17/49	DA	55'		0'	N/A		No Remediation - Shallow Offset @ 1800' MD
05-069-05056	WR Saulcy 3	139'	National	04/17/65	PA	200'		0'	N/A		No Remediation - Shallow Offset @ 2132' MD
05-069-05057	W R Saulcy 3	122'	National	04/25/65	PA	219'		203'	N/A		Option 3 - ReEnter and Plug
05-069-05058	Saulcy (William R) 2	202'	Magpie	11/27/63	PR	197'		3,951'	0		Option 4 - 5K Wellhead and Monitor Pressure
05-069-05059	Trindle 2	194'	Magpie	05/30/63	PR	195'		4,140'	26		Option 4 - 5K Wellhead and Monitor Pressure
05-069-05060	Bunker 1-A	173'	Okmar Oil CO	07/30/63	PA	205'		3,978'	N/A		No Remediation - Abandoned Feb 1968 - TOC in pipe @ 4410'. Casing pulled.
05-069-05061	Trindle 1	238'	Dyer J G	02/07/49	DA	278'		0'	N/A		No Remediation - Shallow Offset @ 1913' MD.
05-069-05063	Warberg, Carl 1-C	246'	Magpie	05/07/65	PR	199'		3,847'	0		Option 4 - 5K Wellhead and Monitor Pressure
05-069-05064	Rudolph Minch 1	248'	Skaer	07/12/63	PA	230'		4,162'	N/A		No Remediation - Abandoned April 1972 - TOC in pipe @ 4246, pulled 3620' of casing
05-069-05065	Weber 1	245'	Magpie	03/20/57	PR	250'		3,875'	35		Option 4 - 5K Wellhead and Monitor Pressure
05-069-05066	Ivers, Dorothy 1-B	532'	Magpie	04/09/63	TA	326'		4,144'	0		Option 4 - 5K Wellhead and Monitor Pressure
05-069-05067	Henry Weber 1	1,512'	Lakota Petr	05/05/65	DA	207'		207'	N/A		Option 3 - ReEnter and Plug
05-069-05068	Warberg (Carla A) 1-D	678'	Magpie	11/14/64	PR	226'		3,790'	0		Option 4 - 5K Wellhead and Monitor Pressure; CBL LABELED OTHER WELLLOG515759.TIF
05-069-05069	Ivers Draper Community 1	680'	National	05/28/68	PA	230'		4,384'	0		Option 3 - Abandoned Aug 2 1968 - TOC in pipe @ 4245. Pulled 3150' of casing.
05-069-05071	C R Brownwood ET AL 1-A	1,953'	National	03/18/64	DA	202'		0'	N/A		TION 3: DA IN 1965, DRILLED TO 5300', CEMENT IN BOTTOM OF SURFACE. NO RECORD OF CEMENT PAST SURFACE
05-069-05072	Brownwood CR 1	1,950'	Skaer	03/18/64	PA	201'		3,933'	N/A		sp of cement in pipe 4255' est. Cmt plug from 1800'-1900'. 5-1/2 casing cut at 3761' and recovered. Verbal completion report
05-069-05073	Pulliam 1A	1,946'	Magpie	06/02/65	TA	199'		3239'	20		Option 4 - 5K wellhead and monitor pressure. 250sxc cement behind 5.5" set at 4944 using 1.3cuft / sxc
05-069-05074	Pulliam A-Gregg Unit 1	2,006'	Skaer	05/17/65	PA	208'		3,574'	N/A		No Remediation Necessary - Abandoned 3-30-1972, TOC in pipe @ 4720 est, pipe cut at 2729'
05-069-05283	INTER-AMERICAN BUNKER 2	1,066'	MAGPIE	01/15/66	PR	267'	62'	4,020'	0		Option 4 - 5K Wellhead and Monitor Pressure
05-069-05295	INTER-AMERICAN BUNKER 1	1,054'	MAGPIE	11/24/65	PR	232'	62'	4,014'	0		Option 4 - 5K Wellhead and Monitor Pressure
05-069-06014	Schwarz 1	224'	Skaer	08/27/67	PA	137'		3,934'	N/A		No Remediation Necessary - Abandoned March 1986 - set cblp @ 4200', TOC in casing @ 4156'. Cut and pulled 4070' of casing
05-069-06027	Minch 1-X	204'	Magpie	11/22/74	PR	117'		4,063'	0		Option 4 - 5K Wellhead and Monitor Pressure
05-069-06030	Schwarz 1-X	178'	Skaer	03/24/75	PA	212'		3,950'	0		No Remediation Necessary - Abandoned Oct 1985, TOC in pipe @ 4714; cut and pulled 3900' of casing.
05-069-06034	MATLAND #1	1,466'	SKAER	12/06/75	PA	222'		2,722'	0		No Remediation Necessary - Abandoned 7-15-85 - CIBP @ 1602, SAND from 1492 to 1602, CIBP @1400, 3sx cmt. Cut 5-1/2 casing
05-069-06037	Hein & Hart 1	256'	Magpie	12/27/75	PR	290'		4,345'	210		Option 4 - 5K Wellhead and Monitor Pressure
05-069-06043	WARBERG #1	1,593'	AMOCO	03/24/76	AL				N/A		No evaluation necessary
05-069-06046	Ivers-Diggs 1-X	661'	Magpie	07/08/76	PA	258'		3,875'	45		No Remediation Necessary - Abandoned 5/14/2019
05-069-06048	Gill -Trindle 1	320'	Magpie	07/30/76	SI	262'		4,138'	N/A		Option 4 - 5K Wellhead and Monitor Pressure
05-069-06074	Milttenberger 1	749'	Operating, INC	12/15/77	PA	205'		3,922'	N/A		No Remediation Necessary - Abandoned 10/2005 - TOC in pipe @ 4326'. Cut and pulled 2406' of casing.
05-069-06078	Weber 1	679'	Operating, INC	01/22/79	PR	204'		4,310'	35		Option 4 - 5K Wellhead and Monitor Pressure
05-069-06079	Stugart 1	255'	Operating, INC	02/09/79	PR	207'		3,430'	0		Option 4 - 5K Wellhead and Monitor Pressure
05-069-06080	Dunning 1	2,628'	Operating, INC	02/02/79	TA	208'		3,620'	0		Option 4 - 5K Wellhead and Monitor Pressure
05-069-06081	Tucker 1	1,726'	Operating, INC	Unknown	SI	238'		4,120'	15		Option 4 - 5K Wellhead and Monitor Pressure
05-069-06088	BUNKER #2-A	1,100'	OPERATING INC	12/09/79	PR	213'	62'	3,836'	0		Option 4 - 5K Wellhead and Monitor Pressure
05-069-06093	Ven Enterprises 1	2,773'	Mission Oil Corp.	03/04/80	PA	200'		3,815'	N/A		quired - abandoned 2/1/89 - toc in casing @ 4253'. Cement plug @ 1750', 1325', and 700'. CBL LABELED "GAMMA RAY L
05-069-06103	Westward 2	3,522'	Harburg Rudolph W	09/03/80	PR	200'		3,844'	0		Option 4 - 5K Wellhead and Monitor Pressure
05-069-06107	Haggarty-Warberg 1	194'	Magpie	11/22/80	PR	201'		4,660'	0		Option 4 - 5K Wellhead and Monitor Pressure
05-069-06109	Weber, Henry 1-A	1,241'	Operating, INC	12/17/80	PA	197'		4,025'	N/A		No Remediation Necessary - abandoned 2009
05-069-06110	Osborn 1	1,910'	Operating, INC	12/10/80	PR	198'		4,035'	5		Option 4 - 5K Wellhead and Monitor Pressure
05-069-06112	Saulcy 3	203'	Operating, INC	03/16/81	PA	210'		4,770'	N/A		No Remediation necessary - abandoned 3/2013 - toc in pipe @ 3144'. Cut and pull 3200 ft of casing
05-069-06116	Osborn 2	1,994'	Operating, INC	10/11/81	PR	253'		4,032'	0		Option 4 - 5K Wellhead and Monitor Pressure
05-069-06118	Warberg E-1	687'	Skaer	11/05/81	DA	200'		4,452'	N/A		No Remediation Necessary - Abandoned 1982 -TOC in pipe @ 4000', and 3000'
05-069-06124	Ollilia 1	1,989'	Enterprises Empire	07/03/81	PA	Unknown		4,265'	N/A		No Remediation necessary. Abandoned in 1982. Cement plug from 4400'-4700', cut and pulled casing.