

FORM  
2

Rev  
05/22

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

403117925

(SUBMITTED)

Date Received:

08/01/2022

APPLICATION FOR PERMIT TO

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

Amend ☐

TYPE OF WELL OIL ☒ GAS ☐ COALBED ☐ OTHER: \_\_\_\_\_

Refile ☒

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: Judy

Well Number: 3-6-3L

Name of Operator: CONFLUENCE DJ LLC

COGCC Operator Number: 10518

Address: 1125 17TH STREET #1550

City: DENVER

State: CO

Zip: 80202

Contact Name: Brittany Rothe

Phone: (303)226-9519

Fax: ( )

Email: brothe@confluencelp.com

FINANCIAL ASSURANCE FOR PLUGGING, ABANDONMENT, AND RECLAMATION

COGCC Financial Assurance

☒ The Operator has provided or will provide Financial Assurance to the COGCC for this Well.

Surety ID Number (if applicable): 20160056

Federal Financial Assurance

☐ In checking this box, the Operator certifies that it has provided or will provide at least this amount of Financial Assurance to the federal government for this Well. (Per Rule702.a.)

Amount of Federal Financial Assurance \$ \_\_\_\_\_

WELL LOCATION INFORMATION

Surface Location

QtrQtr: SWSW Sec: 34 Twp: 1N Rng: 65W Meridian: 6

FNL/FSL

FEL/FWL

Footage at Surface: 770 Feet FSL 919 Feet FWL

Latitude: 40.002660

Longitude: -104.656270

GPS Data:

GPS Quality Value: 1.4

Type of GPS Quality Value: PDOP

Date of Measurement: 06/14/2022

Ground Elevation: 5141

Field Name: WATTENBERG

Field Number: 90750

Well Plan: is ☐ Directional ☒ Horizontal (highly deviated) ☐ Vertical

If Well plan is Directional or Horizontal attach Deviated Drilling Plan and Directional Data.

Subsurface Locations

Top of Productive Zone (TPZ)

Sec: 3 Twp: 1S Rng: 65W

Footage at TPZ: 360 FNL 2360 FWL

Measured Depth of TPZ: 7946

True Vertical Depth of TPZ: 7366

FNL/FSL

FEL/FWL

**Base of Productive Zone (BPZ)**Sec: 10 Twp: 1S Rng: 65WFootage at BPZ: 610 FSL 2360 FWLMeasured Depth of BPZ: 17308True Vertical Depth of BPZ: 7366 FNL/FSL FEL/FWL**Bottom Hole Location (BHL)**Sec: 10 Twp: 1S Rng: 66WFootage at BHL: 610 FSL 2360 FWL

FNL/FSL FEL/FWL

**LOCAL GOVERNMENT PERMITTING INFORMATION**County: WELDMunicipality: N/A

Is the Surface Location of this Well in an area designated as one of State interest and subject to the requirements of §

24-65.1-108 C.R.S.? Yes

Per § 34-60-106(1)(f)(I)(A) C.R.S., the following questions pertain to the Relevant Local Government approval of the siting of the proposed Oil and Gas Location.

SB 19-181 provides that when "applying for a permit to drill," operators must include proof that they sought a local government siting permit and the disposition of that permit application, or that the local government does not have siting regulations. § 34-60-106(1)(f)(I) (A) C.R.S.

Does the Relevant Local Government regulate the siting of Oil and Gas Locations, with respect to this Location? ☒ Yes ☐ No☒ If yes, in checking this box, I hereby certify that an application has been filed with the local government with jurisdiction to approve the siting of the proposed oil and gas location.The disposition of the application filed with the Relevant Local Government is: Approved Date of Final Disposition: 03/19/2018Comments: The WOGLA was approved on 03/19/2018.**SURFACE AND MINERAL OWNERSHIP AT WELL'S OIL & GAS LOCATION**Surface Owner of the land at this Well's Oil and Gas Location: ☒ Fee ☐ State ☐ Federal ☐ IndianMineral Owner beneath this Well's Oil and Gas Location: ☒ Fee ☐ State ☐ Federal ☐ Indian

Surface Owner Protection Bond (if applicable):

Surety ID Number (if applicable):

**MINERALS DEVELOPED BY WELL**

The ownership of all the minerals that will be developed by this Well is (check all that apply):

☒ Fee☐ State☐ Federal☐ Indian☐ N/A**LEASE INFORMATION**

Using standard QtrQtr, Section, Township, Range format describe one entire mineral lease as follows:

\* If this Well is within a unit, describe a lease that will be developed by the Well.

\* If this Well is not subject to a unit, describe the lease that will be produced by the Well.

(Attach a Lease Map or Lease Description or Lease if necessary.)

T1S R65W Sec. 3: N/2Total Acres in Described Lease: 286Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease #

## SAFETY SETBACK INFORMATION

Distance from Well to nearest:

Building: 1046 Feet  
Building Unit: 1216 Feet  
Public Road: 754 Feet  
Above Ground Utility: 1201 Feet  
Railroad: 5280 Feet  
Property Line: 402 Feet

### INSTRUCTIONS:

- Specify all distances per Rule 308.b.(1).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit – as defined in 100 Series Rules.

## OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	407-3338	1280	T1S-R65W Sec 3 & 10: All

Federal or State Unit Name (if appl):

Unit Number:

## SUBSURFACE MINERAL SETBACKS

Enter 5280 for distance greater than 1 mile.

Is this Well within a unit? Yes

If YES:

Enter the minimum distance from the Completed Zone of this Well to the Unit Boundary: 360 Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well within the same unit permitted or completed in the same formation: 400 Feet

If NO:

Enter the minimum distance from the Completed Zone of this Well to the Lease Line of the described lease: Feet

Enter the minimum distance from the Completed Zone of this Well to the Completed Zone of an offset Well producing from the same lease and permitted or completed in the same formation: Feet

## Exception Location

☐ If this Well requires the approval of a Rule 401.c Exception Location, enter the Rule or spacing order number and attach the Exception Location Request and Waivers.

## SPACING & FORMATIONS COMMENTS

**DRILLING PROGRAM**Proposed Total Measured Depth: 17308 FeetTVD at Proposed Total Measured Depth 7366 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 1311 Feet ☐ No well belonging to another operator within 1,500 feetWill a closed-loop drilling system be used? YesIs H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater thanor equal to 100 ppm? No If yes, attach an H<sub>2</sub>S Drilling Plan unless a plan was already submitted with the Form 2A per Rule 304.c.(10).Will there be hydraulic fracture treatment at a depth less than 2,000 feet in this well? NoWill salt sections be encountered during drilling? NoWill salt based (>15,000 ppm Cl) drilling fluids be used? NoWill oil based drilling fluids be used? YesBOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

Beneficial reuse or land application plan submitted? \_\_\_\_\_

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

**CASING PROGRAM**

Casing Type	Size of Hole	Size of Casing	Grade	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	A52A	43	0	80	400	80	0
SURF	13+1/2	9+5/8	J55	36	0	2500	1190	2500	0
1ST	8+1/2	5+1/2	P110	20	0	17308	1873	1730	

☐ Conductor Casing is NOT planned**POTENTIAL FLOW AND CONFINING FORMATIONS**

Zone Type	Formation /Hazard	Top M.D.	Top T.V.D.	Bottom M.D.	Bottom T.V.D.	TDS (mg/L)	Data Source	Comment
Groundwater	Upper Arapahoe	0	0	541	541	501-1000	DWR	
Groundwater	Lower Arapahoe	541	541	1197	1197	501-1000	DWR	
Groundwater	Laramie-Fox Hills	1197	1197	1428	1428	501-1000	USGS	Top & bottom depth from DWR
Groundwater	Upper Pierre	1428	1428	2314	2276	1001-10000	Other	COGCC: Upper Pierre Aquifer Water Quality Study, Project #2141
Confining Layer	Pierre Shale	2314	2276	4767	4666			
Hydrocarbon	Sussex	4767	4666	5054	4945			
Confining Layer	Pierre Shale	5054	4945	5507	5387			
Hydrocarbon	Shannon	5507	5387	5907	5777			
Confining Layer	Pierre Shale	5907	5777	7257	7066			
Subsurface Hazard	Sharon Springs	7257	7066	7277	7082			
Hydrocarbon	Niobrara	7277	7082	7946	7366			

**OPERATOR COMMENTS AND SUBMITTAL**

Comments

Distance from completed zone of this wellbore to nearest completed zone of an offset well within the same unit permitted or completed in the same formation was measured to the proposed Judy 3-5-2L in 2D.

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells was measured to the producing Jordan 34-5 (05-123-12670) Operated by K P Kauffman Company Inc.

This is a Form 2 Refile.

Changes to the original approved Form 2 are: Name change, top of productive interval, bottom hole location, total depth, casing and cement program.

The API numbers being used for these APD's are for permits that have been abandoned by Confluence.

This location has been built; therefore, an OGDG is not required.

This application is in a Comprehensive Area Plan No CAP #: \_\_\_\_\_  
Oil and Gas Development Plan Name \_\_\_\_\_ OGDG ID#: \_\_\_\_\_  
Location ID: 449244

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Andrea Gross

Title: Permit Agent Date: 8/1/2022 Email: agross@upstreampm.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules, applicable orders, and SB 19-181 and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_  
Expiration Date: \_\_\_\_\_

**API NUMBER**

05 123 45934 00

### Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

**COA Type**

**Description**

--	--



## Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	Drilling/Completion Operations	Logging: The Judy 3-4 (API No. 05-123-50294-00) well drilled on the pad was logged with an open-hole Resistivity Log and Gamma Ray Log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "No open-hole logs were run. The Judy 3-4 (API No. 05-123-50294-00) is the well in which open-hole logs were run."
2	Drilling/Completion Operations	Anti-collision: Operator will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within 150 feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators prior to drilling.

Total: 2 comment(s)

### Attachment List

<u>Att Doc Num</u>	<u>Name</u>
403119265	WELL LOCATION PLAT
403119270	DEVIATED DRILLING PLAN
403119271	DIRECTIONAL DATA
403122277	OffsetWellEvaluations Data

Total Attach: 4 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)

## Public Comments

No public comments were received on this application during the comment period.

