

B. J. HUGHES, INC.

CEMENTING SERVICE REPORT

FT. LUPTON
659-0864

NOV 14 1982 HUGHES TOOL COMPANY

Date 10/24/82Company ANADARKO PROD. CO.Well No. A-1Service Ticket No. S 18221

Formation _____

County ADAMSState COLO.BJ Service Foreman T. Melnychuk & S. BRANHAN.Company Representative MR.

REMARKS: 50 sk. cmt. = 10.4 bbl slurry.
10 sk. cmt. = 2 bbl slurry.
5 sk cmt. = 1 bbl slurry.

Trucks Used 1467, 5387

COLO. OIL & GAS CONS. COMM. WELL DATA

Hole Size: 7 7/8" Depth: 6789Casing Size: 8 5/8" Wt. 24# Depth 641Dlg. Fluid Type MUD. Wt. _____

Stage Collars: _____

Contractor: EXETER #2

CEMENT DATA

NO. SACKS	YIELD Cu. Ft./Sk.	CEMENT MIX	CUFF	VOLUME BBLs.	WT.
175	1.17			36.4	15.7

Volume of Displacement 143 bbl TOTAL. Bbl.Cement Circulated N/A. Bbls.Circulation During Job? Yes

Job Detail

TIME	RATE BPM	VOLUME BBL	PRESSURE		
			TUBING	CASING	
10/24 START 6:17 PM Finish 7:00 PM	5			250	PLUG #1 6402' - 6580' 50 sk. 10 bbl H ₂ O Ahead. mix cement with 6 bbl H ₂ O, 2 bbl H ₂ O behind + 88 bbl mud.
START Finish	5			250	PLUG #2 3229' - 3397' 50 sk. 10 bbl H ₂ O Ahead. mix cement with 6 bbl H ₂ O, 3.5 bbl H ₂ O behind + 42.5 bbl mud.
10/25 START 5 AM Finish 5:30	4			150	PLUG #3 503' - 671' 50 sk. circ. mud out of hole with 40 bbl H ₂ O. mix cement with 6 bbl H ₂ O, DISPLACE 7 bbl H ₂ O.
START 7:00 AM Finish 7:30 AM					PLUG #4 Surface - 40' 10 sk. 3 bbl H ₂ O Ahead. mix cement with 1.2 bbl H ₂ O. .5 bbl H ₂ O behind.
START 7:15 Finish 7:30					PLUG mouse hole & RAT hole with 5 sk. cmt. each.

T. Melnychuk
 BJ HUGHES INC.

RC