

DTU 1142 Mancos Silt Recomplete

API #: 05-103-09604

Date: 03/08/2022

NWSE-S27-T2S-R102W-6PM

Elevation: 7081' GR, 7091' KB

Work Order #: PENDING

Rio Blanco County, Colorado

PBTD/TD: 3093'/3167'

Current EOT: 2888'

CONTACT INFORMATION

LEAD	PHONE	LEAD	PHONE
TERRY RICHARDSON	970-629-0316	JESSE SMUTS	970-361-0167
ENGINEER	PHONE	RIG FOREMAN	PHONE
TJ SHELTON	970-629-1222	TRAVIS PETERSON	970-549-7984

WELL DATA:

Tubular Type	Grade	OD (in)	Wt/Len (lb/ft)	Set Depth (ft)	ID (in)	Drift (in)	Collapse (psi)	Burst (psi)	Capacities		
									Gal/ft	ft ³ /ft	Bbl/ft
Surface Casing	J-55	8.625	24.0	216	8.097	7.972	1370	2950	-	-	-
Production Casing	J-55	5.500	15.5	3150	4.95	4.825	4040	4810	0.9997	0.1336	0.0238
Production Tubing	J-55	2.375	4.7	2888	1.995	1.901	8100	7700	0.1624	0.0217	0.0039

Annulus	Capacities		
	Gal/ft	ft ³ /ft	Bbl/ft
Production Casing (5.5" @ 15.5 lbs/ft) - Tubing (2.325")	0.7696	0.1029	0.0183

PERFERATIONS:

Type	Target Formation	Depth (ft)
Proposed	Mancos Silt	2451-2599
Existing	Mancos B	2733-3035

PROCEDURE:

NOTE: Any water that goes in the hole will need to be 2% KCL treated w/ corrosion inhibitor and biocide.

- 1.) MIRU completions unit. Open casing and bleed down well. NDWH & NUBOP. Unseat 2-3/8" tubing and RIH to tag. POOH w/ tubing. PU and CO to PBTD with sand pump if necessary.
- 2.) MIRU perforators w/ packoff pressure equipment. RIH w/ Junk Basket to 2720'. Run correlation log and tie into GR/N log. RIH w/ 5-1/2" CIBP and set @ 2708'. Pressure test to 3850 psi for 15 minutes. TIH w/ 3-1/8" gun and perforate the Mancos Silt as follows w/ 19 gm charge, 0.38" EHD, 180° phasing as follows in Appendix A. RDMO Perforators.
- 3.) MIRU Well Treaters. NUBOP and TIH w/ 2-3/8" tubing with blast joint on top to ~2599'. Load tubing and circulate one annular volume (51 bbls) with 2% KCL. Spot acid across the perms (114 gallons) and shut in for 15 minutes. PU tubing to ~2401'.
- 4.) Break Down Mancos Silt w/ 1000 gallons of 15% HCL plus additives as directed by engineering. Recommended injection rate is 7 BPM diverting with 57 1" x 1.3 SG ball sealers spaced evenly throughout the treatment. If ball off occurs, surge and pump remaining fluids. Displace treatment with 2% KCL. **MAXIMUM PRESSURE IS 3848 psi.**
- 5.) Surge well to release balls.
- 6.) NDBOP & NUWH and flowback line. RD and release WO rig.
- 7.) Fracture treat the Mancos Silt with nitrogen as directed by well treater's procedure. The recommended injection rate is 30 BPM @ 3838 psi max pressure. **START FLOWBACK IMMEDIATELY.** RDMO Well Treaters.
- 8.) Immediately flow back to tanks/pit wide open. Put well online for extended flow test.
- 9.) MIRU WO Rig. RIH to tag. NDWH & NUBOP. CO to CIBP @ 2708'.
- 10.) TIH w/ SN on 2-3/8" tubing. Land tubing w/ EOT @ 2550'. NDBOP & NUWH. RDMO WO Rig. Release to operations for RTP as Mancos Silt well until further notice.

APPENDIX A:

RECOMMENDED PERFORATIONS (SHOTS SUBJECT TO FINAL APPROVAL)	
DEPTH	HOLES
2451	1
2455	1
2459	1
2463	1
2467	1
2471	1
2475	1
2479	1
2483	1
2487	1
2491	1
2495	1
2499	1
2503	1
2507	1
2511	1
2515	1
2519	1
2523	1
2527	1
2531	1
2535	1
2539	1
2543	1
2547	1
2551	1
2555	1
2559	1
2563	1
2567	1
2571	1

2575	1
2579	1
2583	1
2587	1
2591	1
2595	1
2599	1
Total:	38