



**Cement Ticket**

<b>Customer Name</b> Chevron	<b>Date Of Service:</b> 8/2/2022
---------------------------------	-------------------------------------

<b>Location</b> BLEHM N26-17	<b>County</b> Weld County, CO	<b>AFE</b>	<b>Equipment</b> C1003
---------------------------------	----------------------------------	------------	---------------------------

Billing			
Description	Qty	Rate	Total
P and A Charge(Each)			
Mileage(Miles)			
G Cement(Bags)			
Data Acquisition(Each)			
Iron Inspection(Each)			
Sugar(Lbs)			
Water Delivery(Barrels)			

  

Description	Qty	Rate	Total	
Miscellaneous				defoamer
Miscellaneous				retarder
Miscellaneous				rigless p&a charge
Miscellaneous				water bobtail hours
Miscellaneous				Wireline credit for tubing already at depth

<b>Description of Work</b>	<b>Start Time</b> 06:00 am	<b>Stop Time</b> 11:30 am
----------------------------	----------------------------	---------------------------

UWRWE-A2659-ABN Patricia Albidrez Gate to gate: 6:30 am – 11:30 am MOB to location, spot in, rig up, flowback incinerated gas, Status: 2-3/8" 4.7# tubing at 7,535' inside 4-1/2" 11.6# casing, pump down tubing, pump 35 bbl. freshwater, pumped 1 bbl. LCM pill, displaced with 28.3 bbl. waited 30 minutes, established circulation with 59 bbl. of water, pumped 120 bbl. total water, pumped 5 bbl. freshwater spacer, mix and pumped 35 sxs of 15.8# 1.15 cu.ft./sack Class G cement with retarder, 7.2 bbl. of slurry, displaced with 27.5 bbl. to cover from 7,535' to 7,022', RD valve, wash out pump, RD equipment Non rev: pretrip truck, prep for job, loaded cement

Payroll Section						
Employee	Rev Hrs.	Travel Hrs.	Non Rev Hrs.	Total		
Supervisor Rascon, Aron	0.00	0.00	0.00	0.00		0.00
Operator Pena, Marcos	5.00	0.00	0.50	5.50		
Derrick Meza, Abraham	5.00	0.00	0.50	5.50		
FloorHand Soto, Juan I.	5.00	0.00	0.50	5.50		

No UnReported Incidents Per My Signature

\_\_\_\_\_  
Ranger Tool Pusher

\_\_\_\_\_  
Customer/Agent: