

OPERATOR: K.P. Kauffman Company Inc.

WELL: Carl M Cary #1

FIELD: Spindle

API # 05-123-07678

LEASE #:

UIC #:

CNTY: Weld

STATE: CO

SPUD: 5/10/1973

COMP: 6/7/1973

STATUS: PR

WBD DATE: 7/28/2022

FTG:

Q-Q: SWNW

SEC.: 2

TWS: 1N

RGE: 67W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 4978 '

KB: 10 '

GLE: 4968 '

TD (ft): 4845 '

PBTD (ft): 4803 '

12 1/4" Hole
8 5/8" 24# Csg @ 220 '
Cmtd w/ 200 sxs

TOC @ 2825 '
Calc (Assume 1.15 Yield)

7 7/8" Hole
4 1/2" 10.5# Csg @ 4848 '
Cmtd w/ 400 sxs

Sussex Perfs
4724'-4746'

PBTD (ft): 4803 '

TD (ft): 4845 '

CASING RECORD

| HOLE (in) | SIZE (in) | WT (lb/ft) | GRADE | TOP (ft) | BTM (ft) |
|---------------|--------------|-------------|-------|----------|-------------|
| <u>12 1/4</u> | <u>8 5/8</u> | <u>24</u> | | <u>0</u> | <u>220</u> |
| <u>7 7/8</u> | <u>4 1/2</u> | <u>10.5</u> | | <u>0</u> | <u>4848</u> |

TUBING RECORD

| SIZE (in) | WT (lb/ft) | GRADE | JOINTS | BTM (ft) |
|--------------|------------|-------------|------------|-------------|
| <u>2 3/8</u> | <u>4.7</u> | <u>J-55</u> | <u>154</u> | <u>4711</u> |

PERFORATION RECORD

| ZONE | TOP (ft) | BTM (ft) | HOLES | STAGE | STATUS |
|---------------|-------------|-------------|-----------|-------|--------|
| <u>Sussex</u> | <u>4724</u> | <u>4746</u> | <u>20</u> | | |