

OPERATOR: K.P. Kauffman Company Inc.

WELL: CHRISTIANSEN UNIT #1

FIELD: SPINDLE

API # 05-123-07662

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 3/6/1973

COMP: 3/27/1973

STATUS: PR

WBD DATE: 8/4/2022

FTG:

Q-Q: SENE

SEC.: 17

TWS: 2N

RGE: 66W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 4928 '

KB: 8 '

GLE: 4920 '

TD (ft): 4760 '

PBTD (ft): 4714 '

12 1/4" Hole
8 5/8" 24# Csg @212
Cmtd w/ 200 sxs

TOC @ 2741
Calc Assuming 1.15 yield

7 7/8" Hole
4 1/2" 10.5# Csg @4760
Cmtd w/ 400 sxs

SUSSEX Perfs
4622'-4648'

PBTD (ft): 4714 '

TD (ft): 4760 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
12 1/4	8 5/8	24		0	212
7 7/8	4 1/2	10.5		0	4760

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
SUSX	4648	4622	12		

Production Notes

CEMENTING RECORD for 4 1/2 casing:
1st Stage 200 sx 50-50 pozmix
2nd Stage 200 sx 50-50 pozmix