

OPERATOR: K.P. Kauffman Company Inc.

WELL: HINGLEY #2

FIELD: SPINDLE

API # 05-123-09325

LEASE #:

UIC #:

CNTY: WELD

STATE: CO

SPUD: 1/10/1978

COMP: 10/29/1979

STATUS: PR

WBD DATE: 8/9/2022

FTG:

Q-Q: SENE

SEC.: 28

TWS: 2N

RGE: 68W

BY:

CURRENT WELLBORE DIAGRAM

KBE: 4982 '

KB: 10 '

GLE: 4972 '

TD (ft): 5067 '

PBTD (ft): 5027 '

12.25" Hole
8.625" 24# Csg @536 '
Cmtd w/175 sxs

Squeeze @ 732'
Cmtd w/ 150 sxs
TOC @ surface
Calc Assuming 1.15 yield

TOC @ 3248 '
Calc Assuming 1.15 yield

7.875" Hole
4.5" 10.5# Csg @5015 '
Cmtd w/350 sxs

SUSSEX Perfs
4493'-4534'

Bridge Plug @ 4700'

SHANNON Perfs
4962'-4978'

PBTD (ft): 5027 '

TD (ft): 5067 '

CASING RECORD

HOLE (in)	SIZE (in)	WT (lb/ft)	GRADE	TOP (ft)	BTM (ft)
12 1/4	8 5/8	24		0	536
7 7/8	4 1/2	10.5		0	5015

TUBING RECORD

SIZE (in)	WT (lb/ft)	GRADE	JOINTS	BTM (ft)

PERFORATION RECORD

ZONE	TOP (ft)	BTM (ft)	HOLES	STAGE	STATUS
SUSSEX	4493	4534	16		
SHANNON	4962	4978	17		